

CERTIFIED RECORD OF LAND CORNER MONUMENTATION

T 4N , R 37E. , W.M.

Corner Code No. Z-21  
Note: Monument marked as shown below

History of original corner establishment:

This corner was originally established by George S. Pershin, U.S. Deputy Surveyor, under Contract No. 304, dated September 19, 1878.


The original notes states:

Set Spruce post on nearly level for corner to sections 1, 2, 35, & 36 from which:

A fir 10 in. diam. bears S 48° E, 229 links.  
A fir 48 in. diam. bears N 43° W, 188 links.

No other green trees near.

In 1976, under Survey No. L-56-B, the corner was re-established by single proportion measurement and monumented with a 2 1/2" brass cap on a 2" by 31" iron pipe.



Corner No.  
Compass Declination: 18.0°

Description of corner evidence found:

Found a 2 1/2" brass cap on a 2 1/2" galvanized iron pipe 6" out of ground and in good condition from which:

A 18" white fir bears N 51° E, 110.0', with scribes visible on partly healed double blaze.

A 19" white fir bears S 32° E, 105.0', with healed double blaze.

A 18" white fir bears S 21° W, 51.0', with partly healed double blaze.

A 16" Douglas fir bears N 71° W, 60.0', with healed double blaze.

All bearing trees referencing the corner were marked by RPE 2808 under Survey No. L-56-B.

Description of monument and accessories established to perpetuate the original location of this corner:

Maintained monument by mounding with earth.

Put witness corner sign on steel fence post East of corner.

All bearing trees have U.S.F.S. bearing tree signs or County bearing object signs attached.

REGISTERED  
PROFESSIONAL  
LAND SURVEYOR

*William R. Wells*

OREGON  
JULY 22, 1977  
WILLIAM R. WELLS  
1106

Office of..... County of.....

State of....., I hereby certify that the within instrument was filed in this office for record on the..... day of....., 19.....

..... by .....  
(COUNTY OFFICIAL) (DEPUTY)

Form R6-7100-57 (9/71)

RECEIVED BY

Umatilla County Surveyor

Date 9-9

Rec'd By JK

No. 91-75-C

☆ GPO-788-276