

CERTIFIED RECORD OF LAND CORNER MONUMENTATION

T 4N, R 37E. , W.M.

Corner Code No. Z-23

Note: Monument marked as shown below

History of original corner establishment:


This corner was originally established by George S. Pershin, U.S. Deputy Surveyor, under Contract No. 304, dated September 19, 1878.

The original notes state:

Set fir post on level for 1/4 section corner from which:

A fir 24 in. diam. bears N 54°E, 115 lks dist.
A spruce 8 in. diam. bears S 15°W, 42 lks dist.

In 1976, under Survey No. L-56-B, the corner was re-established by siggle proportion measure and monumented with a 2 1/2" brass cap on a 2" by 31" iron pipe.



Corner No.

Compass Declination: 18.0°

Description of corner evidence found:

Found a 2 1/2" brass cap on a 2 1/2" galvanized iron pipe 6" out of ground and in good condition from which:

A 10" white fir bears N 85 1/2°W, 84.0', with scribes visible on a partly healed double blaze.

A 12" Englemann spruce bears S 09°E, 72.0' with a healed double blaze.

The two bearing trees noted above were marked by RPE 2808 in Survey L-56 B.

Description of monument and accessories I established to perpetuate the original location of this corner:

Maintained corner by mounding with earth.

Marked 2 new bearing trees:

A 10" lodge pole pine bears N 63 1/2°E, 38.2', scribed 1/4 S36 BT.

A 10" alpine fir bears S 27°W, 11.2', scribed 1/4 S1 BT.

Attached bearing object signs to new bearing trees. The bearing trees by RPE 2808 have U.S.F.S. bearing tree signs attached.

There is a steel fence post to the East with a witness corner sign attached.

REGISTERED

PROFESSIONAL

LAND SURVEYOR

William R. Wells

OREGON

JULY 22, 1977

WILLIAM R. WELLS

1106

Office of..... County of.....

State of....., I hereby certify that the within instrument was filed in this office

for record on the..... day of....., 19.....

(COUNTY OFFICIAL)

(DEPUTY)

Form R6-7100-57 (9/71)

RECEIVED BY

Umatilla County Surveyor

☆ OPO-798-276

Date 9-91

Rec'd By KK

No. 91-75-C