


CERTIFIED RECORD OF LAND CORNER MONUMENTATION

History of original corner establishment:

Corner established in 1833 by General Land Office.  
(Contract Survey)

Original survey record states: Set a basalt stone,  
15 x 10 x 6 ins., 10 ins. in the ground for 1/4  
Sec. Cor., marked 1/4 on N. face; from which,

A pine, 24 ins. diam. brs. S.38° E., 310 lks. dist.,  
marked 1/4 S 7 B T and raised a mound of stone, 2 ft. base 1 1/2  
ft. high N. of Cor.



E-3

Description of corner evidences found:

Found a basalt stone 15 x 10 x 6 ins. marked 1/4 on one side, also a mound of stone from which a pine, now 36" in diameter, bears S.38° E. at 310 links distant. The pine has a Boise Cascade Co. location poster attached. The old blaze has been opened up (not by me) enough to show the old scar and scribe marks.


Description of monument and accessories I established to perpetuate the original location of this corner

On the south side of the mound of stone, I set a 2" diameter pipe 36" long, with the bottom flared and a 3" bronze disk brazed to the top, 24" in the ground; set the stone marked 1/4 on the side in the hole and backfilled with earth and stones.

The disk is stamped thus



From the pipe monument a red fir 28" in diameter bears S.40° W. at 74 feet distant. I placed a Forest Service location poster and a 7"x 10" yellow Attention poster on the tree. I blazed the tree and marked it 1/4 S 7 B T



Office of County Surveyor County of Umatilla  
 State of Oregon, I hereby certify that the within instrument was filed in this office  
 for record on the 1st day of October, 1957, at 2:30 o'clock P.m., (signed)  
*A. J. Lommason* by \_\_\_\_\_  
 (COUNTY OFFICIAL) (DEPUTY)