

**CERTIFIED RECORD OF LAND CORNER MONUMENTATION**

E-5


**History of original corner establishment:**

Corner established by Robert F. Omeq, U.S. Deputy Surveyor, under his Contract No. 761, dated June 16, 1905.

Surveyor General records state:

Set basalt stone 15x8x6 ins. 10 ins. in the ground for cor. of secs. 5,6,7 & 8, marked with 5 notches on E and S edges; from which,

- A pine 8 ins diam bears N64°E, 109 lks dist marked T4NR38ES5 BT.
- A pine 8 ins diam bears S30½°E, 109 lks dist marked T4NR38ES8 BT.
- A pine 30 ins diam bears S27½°W, 221 lks dist marked T4NR38ES7 BT.
- A pine 18 ins dia, bears N56½°W, 122 lks dist marked T4NR38ES6 BT.



**Description of corner evidence found:**

Found a basalt stone 15x8x6" in mound of stone, could not identify any notches, from which,

- A 17" ponderosa pine with scribes visible on opened blaze brs S35½°E, 68.9'.(OBT)
- A 24" dead standing ponderosa pine snag 10' high brs S23 3/4°W, 143.1' with scribes visible on opened blaze.(OBT)
- A 16" dead standing ponderosa pine brs N66 3/4°W, 77.0' with scribes visible on opened blaze.(OBT)

**Description of monument and accessories established to perpetuate the original location of this corner:**

At position of found stone...

Set 2½" aluminum cap on 2½" x 30" aluminum pipe 18" in ground to bedrock & surrounded with mound of earth & stone. Set 6' fence post North of corner with sign 54-4 attached. Cap marked as shown in corner diagram. Buried corner stone in new mound.

New bearing trees established:

- A 16" ponderosa pine brs N32°E, 55.8' scribed T4NR38ES5 BT.
- A 22" ponderosa pine brs S17°E, 46.5' scribed T4NR38ES8 BT.
- A 19" ponderosa pine brs S59½°W, 92.8' scribed T4NR38ES7 BT.
- A 15" ponderosa pine brs N44½°W, 26.8' scribed T4NR38ES6 BT.

New bearing trees have a brass washer stamped PLS 1106 nailed to face of blaze. Attached sign 54-3 & 54-4 to each BT and painted face of blaze & 6" red band around each BT.

Compass declination 12° East.

I hereby certify that the above described corner monument was properly remonumented by me on August 12, 1988.

REGISTERED  
PROFESSIONAL  
LAND SURVEYOR

*William R. Wells*

OREGON  
JULY 22, 1977  
WILLIAM R. WELLS  
1106

Office of..... County Surveyor..... County of..... Umatilla.....  
State of..... Oregon..... I hereby certify that the within instrument was filed in this office  
for record on the..... 17<sup>th</sup> day of..... October..... 1988.....  
David H. Kumbier..... by..... Kathleen A. Amberg.....  
(COUNTY OFFICIAL) (DEPUTY)

Form R6-7100-57 (9/71)

RECEIVED BY  
Umatilla County Surveyor  
Date 10-88  
Rec'd By A  
No. 88-64-B