


CERTIFIED RECORD OF LAND CORNER MONUMENTATION

G-1

History of original corner establishment:

Corner was established as part of this survey, on the East line of Sec.12, T 4 N R 37 E, midway latitudinally between the N.W. and S.W. corners of Sec.7.



Description of corner evidence found:

None.

Description of monument and accessories established to perpetuate the original location of this corner:

At position determined by survey...

Set 2 1/2" aluminum cap on 2 1/2" x 30" aluminum pipe 15" in ground to bedrock & surrounded with mound of earth & stone. Set 6' fence post South of corner with sign 54-9 attached. Cap marked as shown in corner diagram.

New bearing trees established;

- A 20" ponderosa pine brs S18 1/2° E, 23.6' scribed 1/4S7 BT.
- A 16" ponderosa pine brs N54 1/2° E, 55.8' scribed 1/4S7 BT.

New bearing trees have a brass washer stamped PLS 1106 nailed to face of blaze. Attached sign 54-3 & 54-9 to each BT and painted face of blaze & 6" red band around each BT.

Compass declination 19° East.

I hereby certify that the above described corner monument was properly established by me on August 24, 1988.

REGISTERED
 PROFESSIONAL
 LAND SURVEYOR

William R. Wells

OREGON
 JULY 22, 1977
 WILLIAM R. WELLS
 1106

Office of..... County Surveyor..... County of Umatilla
 State of Oregon..... I hereby certify that the within instrument was filed in this office
 for record on the 17th day of October, 1988
 David H. Keumben..... by Kathleen K. Ambrey
 (COUNTY OFFICIAL) (DEPUTY)

Form R6-7100-57 (9/71)

RECEIVED BY

Umatilla County Surveyor
 Date 10-88
 Rec'd By KA
 No. 88-64-B

*GPO-591-971, 1988