


CERTIFIED RECORD OF LAND CORNER MONUMENTATION

History of original corner establishment:

None. Corner established with this survey.

H-3



Description of corner evidence found:

None.

Description of monument and accessories established to perpetuate the original location of this corner:

At position determined by survey...

Set 2 1/2" aluminum cap on 2 1/2" x 30" aluminum pipe 24" in ground to bedrock & surrounded with mound of earth & stone. Set 6' fence post North of corner with signs 54-9 & 54-2 attached. Cap marked as shown in corner diagram.

New bearing trees established:

A 14" ponderosa pine brs N53 1/2° W, 63.1' scribed C-S1/16S7 BT.

A 28" ponderosa pine brs N14° W, 31.9' scribed C-S1/16S7 BT.

New bearing trees have a brass washer stamped PLS 1106 nailed to face of blaze. Attached sign 54-3 & 54-9 to each BT and painted face of blaze & 6" red band around each BT.

Compass declination 16° East.

I hereby certify that the above described corner monument was properly established by me on August 31, 1988.

REGISTERED
PROFESSIONAL
LAND SURVEYOR

William R. Wells

OREGON
JULY 22, 1927
WILLIAM R. WELLS
1106

Office of...County...Surveyor..... County of Umatilla.....

State of Oregon..... I hereby certify that the within instrument was filed in this office

for record on the 17th day of October..... 1988

David H. Kauder by Kathleen Ambruce

(COUNTY OFFICIAL)

(DEPUTY)

RECEIVED BY

Umatilla County Surveyor

Date 10-8-88

Rec'd by [Signature]

No. 88-64-B