

OREGON CORNER RESTORATION FORM

Section: 13

Township: 4 North

Range: 37 East, W.M.

County: Umatilla

Date: 08/04/2000

Corner Designation: L -25, East 1/4 corner of Section 13

Previous Renewals/Surveys, etc.: This corner was originally set by U.S. Deputy Surveyor George S. Pershin, under his contract No. 304 dated September 19, 1878. The Surveyor General's notes state "set fir post on N.W. face of Spur for 1/4 Sec. cor. A fir 8 in. diam., brs. N15°E 191 lks. dist. A pine 7 in. diam. brs. N18°W 224 lks. dist.

Robert F. Omeg revisited this corner as part of his resurvey of the East line of the Township under his contract No. 761 dated June 19, 1905. The Surveyor General's notes state "The post and described by the Surveyor General are destroyed. The stumps of the bearing trees alone remain. I re-establish the cor. at the same point as follows: Set a lava stone 12x12x8 ins. 8 ins. in the ground for 1/4 Sec. Cor., marked 1/4 on W. face, and raised a mound of stone, 2 ft. base and 1 ft. and a half high W. of Cor."

Monument(s) & Accessories Found (Condition & Source): No evidence of the original or re-established corner could be found.

Monument Detail: T4N
R37E R38E
1/4
S13 + S18
2000
LS 2820

Monument Set (Procedures & Description): At the position determined by survey, using the broken boundary method for the restoration of lost corners, per section 5-36 of the "Manual of Surveying Instructions 1973". Set a 1"x 30" galvanized iron pipe 28" in the ground with a 2 1/2" brass cap attached.

New Accessories: Set 6' carsonite post 3' North of the corner with survey monument and forest boundary stickers attached. A 30" Douglas fir bears N31°E 33.3 feet marked 1/4 S18 BT. A 20" Douglas fir bears N80°E 12.1 feet marked 1/4 S18 BT. A 18" white fir bears S69°W 15.0 feet marked 1/4 S13 BT. A 26" Douglas fir bears N39°W 37.0 feet marked 1/4 S13 BT.

All bearing trees have a 6" wide red band painted around them and bearing tree signs and survey monument signs attached.

Location & Comments: This corner is located on a timbered, Northwesterly facing slope overlooking Tamarack Basin and is a considerable hike from the nearest road.

Compass Declination:

19° East

Firm/Agency: Tomkins Land Surveying, Inc.

20 E. Poplar, Suite 204

Walla Walla WA 99362

Party Chief: Josh Martin

Notes: Josh Martin

Witness: Ryan Laughery

Surveyor's Seal

REGISTERED PROFESSIONAL LAND SURVEYOR

Greg E. Flowers

OREGON JUNE 30, 1997 GREG E. FLOWERS 02820LS

RENEWS 12/31/01

12/15/00

RECEIVED BY

Umatilla County Surveyor

Date 12-00

Rec'd By SM

No. 00-258-C