

USDA-FOREST SERVICE

Index File No. FF F. 76-03.06


CORNER RECORD (SEARCH)

(Ref. FSM 7151.4)

Tract or Survey No. 061411 Cor. No. 2

T 4N R. 38E R.D. Walla Walla County Umatilla
 Merid. Willamette N.F. Umatilla State Oregon

CORNER DIAGRAM
 TR061411



DESCRIBE CORNER MONUMENT FOUND
 None. This corner was established and monumented as part of this survey.

DESCRIBE BEARING TREES OR OTHER OFFICIAL ACCESSORIES FOUND
 None.

PHOTO IDENTIFICATION DATA

Photo No. _____
 Filed At. _____
 Object Ident. _____
 Ident. By _____
Signature

DESCRIBE CORNER LOCATION RELATIVE TO NEAR-BY FEATURES, ALSO HOW TO REACH CORNER
 Corner is located on flat ground, near cabins, East of the North-South centerline of Section 7 and about 100' North of the Walla Walla River.

PLANE COORDINATE POSITION DATA

State _____ Zone _____
 X _____
 Y _____
 Estab. By _____
Agency

Signature Will R. Wells Title PLS Division _____ Headquarters Pendleton, OR Date 9-26-01 FS-7100-52 (3/68)

CORNER RECORD (PERPETUATION)

MONUMENT: DESCRIBE NEW MONUMENT SET, OR WORK DONE TO PRESERVE EXISTING MONUMENT

At position determined by survey, set a 2 1/2" x 30" aluminum pipe with 2 1/2" aluminum cap, 24" in the ground surrounded by a mound of earth and stone. Set steel fence post Southwest of corner and attached signs 54-2 and 54-4 to post. Cap is marked as shown in diagram.

ACCESSORIES : DESCRIBE NEW BT'S WITNESS OBJECTS ETC. ESTABLISHED, OR WORK DONE TO PRESERVE EXISTING EVIDENCE

A 20" ponderosa pine bears N41 1/2°E, 18.4', scribed COR 2 TR061411 BT-BT on double blaze. An 11" Douglas fir bears S67 1/2°E, 21.8', scribed COR 2, TR061411 BT-BT on double blaze. Painted face of blazes only, did not attach signs to bearing trees. Nailed brass washer stamped "PLS 1106" on bottom of blaze of each bearing tree.

Work Done By W.R. Wells Title PLS Date 08/01 State Registration No. or Agency PLS 1106
Certified Cor. Record Prepared? Yes No Filed At: Um. Co. Sur. Off. Date 09/01

REMARKS

Witnessed by:
Jason Wells, LSIT
Mark Hammersla

Index File No. T. 4N R. 38E M. Willamette Tract or Surv. No. 061411 Cor. 2