

CERTIFIED RECORD OF LAND CORNER MONUMENTATION

History of original corner establishment:

Index: R-3

One Quarter Corner, Secs. 19 & 30, T4N, R38E, WM.

Corner originally set by Frank Campbell in contract 468 dated 1883. His record reads:
Set basalt stone 16x10x5 for 1/4 Sec. Cor.

1	DIAGRAM	1
1		1
1		1
1	1 S19	1
1	- - -	1
1	4 S30	1
1	1939	1
1		1
1		1
1		1
1		1

In 1939, Otis Gould and Group 234 replaced the stone with a brass cap. His record reads:
Set an iron post, 3 ft. long, 1 in. diam., 27 ins. in the ground, with the original stone deposited at the base, for 1/4 sec. cor., with brass cap marked(see diagram) from which:

A fir, 10 ins diam., bears N.34°E., 260 lks. dist., marked 1/4 S 19 BT. No other bearing trees available. Raise a mound of stone , 3 ft base, 2 ft. high, N. of cor.

Description of corner evidence found:

Found 2 1/2" GLO brass cap in good condition in a mound of stone. A single bearing tree which bears N34°E, 172', is rotted with no recognizable markings.

Description of monument and accessories I established to perpetuate the original location of this corner:

I set the following new witness trees:

A 22" dbh Alpine Fir bears N57°55'E, 189.6', scribed 1/4 S19 BT.

A 5/8" rebar with 2" Al cap bears N67°10'W, 48.5', stamped BO Cor S67°10'E 48.5'.

A 5/8" rebar with 2" Al cap bears S30°32'W, 47.7', stamped BO Cor N30°32'E 47.7'. Rebar is exposed 8".

A 5/8" rebar with 2" Al cap bears S73°24'E, 48.4', stamped BO Cor N73°24'W 48.4'. Rebar is exposed 8".

The bearings are based on traverse control stations and are true.

A brass washer stamped ORLS852 and WAL5 13922 is attached between the letters B and T with a brass screw on each new tree. All the BT's have Bearing Tree and Land Survey Monument signs attached. A red stripe is painted around each tree at chest height.

This work was done August 17, 1995 and witnessed by Stephan Haddock.

REGISTERED
PROFESSIONAL
LAND SURVEYOR

David L. Haddock

OREGON
JULY 12, 1968
DAVID L. HADDOCK
852

Office of Survey County of Umatilla
State of Oregon, I hereby certify that the within instrument was filed
in this office for record on the 23rd day of October, 1995.
_____ by _____

(COUNTY OFFICIAL)

(DEPUTY)

RECEIVED BY
Umatilla County Survey
Date 10-95
Rec'd by KK
No. 95-179-B