

T-13

**CERTIFIED RECORD OF LAND CORNER MONUMENTATION**


**History of original corner establishment:**

Corner established by Frank Campbell under G.L.O. contract number 468 dated April 12, 1883.

**Surveyor General's records state:**

Set a basalt stone 13" x 10" x 6", 9" in ground for 1/4 corner marked 1/4 on W face from which

A fir 18" dia. bears S 80° E., 56 lks dist. marked 1/4 S BT  
A fir 20" dia. bears N 78° W., 98 lks dist. marked 1/4 S BT



T-13

**Description of corner evidence found:**

Found a basalt stone 13" x 10" x 6" in place 7" above ground with 1/4 chisled on west face and an X chisled on top point

A badly decomposed stump bears N 78° W., 98 lks (64.7 ft.) for sec. 28 BT N1 visible scribing  
A nearly completely decomposed stump bears S 80° E., 56 lks (37 ft.) for sec. 27 BT No visible scribing

**Description of monument and accessories established to perpetuate the original location of this corner**

Set a 2 1/2" brass cap on 2" iron pipe 31" long 6" above ground in earth and rock mound with a 6' steel fence post with sign 54-4 attached alongside.

**new bearing trees:**

A pine 10" dia. bears S 47° E., 6.0 ft dist marked 1/4 S 27 BT  
A fir 9" dia. bears N 77° W., 25.5 ft. dist marked 1/4 S 28 BT

Note: I buried stone on north side of brass cap monument.



Office of Surveyor County of Umatilla  
 State of Oregon, I hereby certify that the within instrument was filed in this office  
 for record on the 26 day of Aug., 1976  
 \_\_\_\_\_ by \_\_\_\_\_  
 (COUNTY OFFICIAL) (DEPUTY)