

CERTIFIED RECORD OF LAND CORNER MONUMENTATION

T 4N, R 38E., W.M.

Corner Code No. T-15


Note: Monument marked as shown below

History of original corner establishment:

This corner was originally established by Victor Mc Lind as shown on Record Map No. R-176-C. The Map states:

Set 2" by 30" galv. iron pipe with brass cap from which:

New BT, a spruce, 12" diam., scribed "C 1/4 S27 BT" bears N 78° E, 67.3';
New B1, a spruce, 10" diam., scribed "C 1/4 S27 BT" bears N 05° E, 47.2';



Corner No.
Compass Declination: 18.0°

Description of corner evidence found:

Found 2 1/2" brass cap on 2 1/2" galvanized iron pipe flush with ground from which:

A 10" broke, blowdown Englemann spruce bears N 5°W, 47.2' with visible scribes on double blaze. (Mc Lind)
A 13" Englemann spruce bears N 82°E, 67.3' with partly healed double blaze. (Mc Lind)

Description of monument and accessories I established to perpetuate the original location of this corner:

Marked 4 new bearing trees:

A 12" Englemann spruce bears N 53 1/2°W, 45.4' scribed C 1/4 S27 BT.
A 15" Englemann spruce bears N 68 1/2°W, 27.2' scribed C 1/4 S27 BT.
A 13" Englemann spruce bears S 82 1/2°W, 36.7' scribed C 1/4 S27 BT.
A 8" alpine fir bears S 16 1/2°E, 36.3' scribed C 1/4 S27 BT.

New bearing trees have a brass washer stamped PLS 1106 nailed to face of blaze. Attached signs 54-3 and 54-9 and painted face of blaze and a 6" red band around each bearing tree.

Set steel fence post East of corner and attached signs 54-2 and 54-9.

Note: Cleaned up around corner monument and mounded earth around it.

REGISTERED PROFESSIONAL LAND SURVEYOR
<i>William R. Wells</i>
OREGON JULY 22, 1977 WILLIAM R. WELLS 1106

Office of..... County of.....
State of....., I hereby certify that the within instrument was filed in this office
for record on the..... day of....., 19....
..... by
(COUNTY OFFICIAL)

RECEIVED BY

Umatilla County Surveyor

Date 1-92
Rec'd By KK
No. 92-01-R