

USDA-FOREST SERVICE

Index

File No. T-15

CORNER RECORD (SEARCH)

(Ref. FSM 7151.4)

Tract or

Survey No. \_\_\_\_\_

Cor.

No. \_\_\_\_\_

T 4N R. 38E

R.D. Walla Walla County Umatilla

Merid. Willamette

N.F. Umatilla State Oregon

CORNER DIAGRAM



T4N R38E  
C 1/4 S27  
1980  
RLS 934

DESCRIBE CORNER MONUMENT FOUND

Found 2 1/2" brass cap on a 2 1/2 inch galv. iron pipe, flush with the ground.

DESCRIBE BEARING TREES OR OTHER OFFICIAL ACCESSORIES FOUND

A 10" broken, blown down englemann spruce bears N 5°W, 47.2' with visible scribes on double blaze. (RLS 934).  
A 13" englemann spruce bears N 82°E, 67.3' with partly healed double blaze. (RLS 934).

PHOTO IDENTIFICATION DATA

Photo No. \_\_\_\_\_  
Filed At. \_\_\_\_\_  
Object Ident. \_\_\_\_\_  
Ident. By \_\_\_\_\_  
*Signature*

DESCRIBE CORNER LOCATION RELATIVE TO NEAR-BY FEATURES, ALSO HOW TO REACH CORNER

Corner is located in logged area about 150' south of the north edge of a clearcut. Walk to corner from wth road about 500' to the west.

PLANE COORDINATE POSITION DATA

State \_\_\_\_\_ Zone \_\_\_\_\_  
X \_\_\_\_\_  
Y \_\_\_\_\_  
Estab. By \_\_\_\_\_  
*Agency*

*Signature*  
Will R. Wells

*Title*  
PLS

*Division*

*Headquarters*  
Pendleton, OR

*Date*  
9/4/91

FS-7100-52 (3/88)

**CORNER RECORD (PERPETUATION)**

**MONUMENT: DESCRIBE NEW MONUMENT SET, OR WORK DONE TO PRESERVE EXISTING MONUMENT**

Cleaned up around the corner monument and mounded earth around it.  
Set steel fence post east of corner and attached sign 54-3 and 54-9.

**ACCESSORIES : DESCRIBE NEW BT'S WITNESS OBJECTS ETC. ESTABLISHED, OR WORK DONE TO PRESERVE EXISTING EVIDENCE**

Marked 4 new bearing trees:

- A 12" englemann spruce bears N  $53\frac{1}{2}^{\circ}$ W, 45.4' scribed  $C\frac{1}{4}$  S27 BT.
- A 15" englemann spruce bears N  $68\frac{1}{2}^{\circ}$ W, 27.2' scribed  $C\frac{1}{4}$  S27 BT.
- A 13" englemann spruce bears S  $82\frac{1}{2}^{\circ}$ W, 36.7' scribed  $C\frac{1}{4}$  S27 BT.
- A 8" alpine fir bears S  $16\frac{1}{2}^{\circ}$ E, 36.3' scribed  $C\frac{1}{4}$  S27 BT.

New bearing trees have a brass washer stamped PLS 1106 nailed to face of blaze. Attached sign 54-3 and 54-9 and painted face of blaze and a 6" red band around all bearing trees.

Work Done By W.R. Wells Title PLS Date 9/4/91 State Registration No. 1106  
or Agency

Certified Cor. Record Prepared? Yes  No  Filed At Umatilla Co. Surveyor Off. Date 12/31

REMARKS

Index File No. T-15 T.4N R.38E M. Will. Tract or Surv. No.

Cor.