

USDA-FOREST SERVICE

INDEX

CORNER RECORD (SEARCH)

(Ref. FSM 7151.4)

FILE NO. T-2 Tract or Survey No. _____ Cor. No. _____
 T. 4 N R. 38 E R.D. Walla Walla County Umatilla
 Merid. Willamette N.F. UNATILLA State Oregon

CORNER DIAGRAM T4N R38E 1 DESCRIBE CORNER MONUMENT FOUND

1 W1/16 1 Corner not previously set.
 1 C----C 1
 N S30 1
 1 1995 1
 1 PLS 852 1

1 DESCRIBE BEARING TREES OR OTHER OFFICIAL ACCESSORIES FOUND

1 Corner not previously set.

PHOTO IDENTIFICATION DATA 1

o No. _____ 1
 Filed At. _____ 1
 Object Ident. _____ 1
 Ident. By _____ 1
 Signature _____ 71

PLANE COORDINATE POSITION DATA 1 DESCRIBE CORNER LOCATION RELATIVE TO NEAR-BY FEATURES, ALSO HOW TO REACH CORNER

State _____ Zone _____ 1 The corner may be reached by traveling Highway 204 west from the Tollgate Store 1 mile to
 X _____ 1 the point where the Highway passes under a high voltage power line. Follow the northerly
 Y _____ 1 edge of the power line clearing about 300' east to where it crosses the posted Forest
 Estab. By _____ 1 Service boundary line. Follow this posted line north 1260' to the corner.
 Agency _____ 81

Signature _____ Title _____ Division _____ Headquarters _____ Date _____ FS-7100-52 (3/68)
 Surveyor _____ Pendleton, OR 9-04-95

CORNER RECORD (PERPETUATION)

MONUMENT : DESCRIBE NEW MONUMENT SET, OR WORK DONE TO PRESERVE EXISTING MONUMENT

Set 2 1/2" x 30" aluminum pipe and cap 26" into the ground with a 30" mound of stone. Stamped the cap as shown in the corner diagram on the opposite side of this card.

9

ACCESSORIES : DESCRIBE NEW BT'S WITNESS OBJECTS ETC. ESTABLISHED, OR WORK DONE TO PRESERVE EXISTING EVIDENCE

Set new bearing trees.

A 16" dbh White Fir bears S41°40'W, 23.4' scribed CW 1/16 S30 BT.

A 24" dbh White Fir bears S42°05'W, 10.4' scribed CW 1/16 S30 BT.

A brass washer stamped ORLS 852 and WALS 13922 is nailed between the letters B and T on each tree with a brass screw. All the BT's have Bearing Tree and Land Survey Monument signs attached. A red band is painted around each tree at chest height.

10

Work Done By David L. Haddock Title Land Surveyor Date 8-14-95 State Registration No. PLS 852
Certified Cor. Record Prepared? x Yes No Filed At: Umatilla County Surveyor Date 9-95 11

REMARKS

12

Index File No. T-2 T. 4 N. R. 38 E. M. Willamette Tract or Surv. No. Cor. 13