

CERTIFIED RECORD OF LAND CORNER MONUMENTATION

History of original corner establishment:

Index: T-3

Center One Quarter Corner, Sec. 30, T4N, R38E, WM.

Corner not previously set.

1	DIAGRAM	1
1		1
1	T4N R38E	1
1	1	1
1	C ---.S30	1
1	4	1
1	1995	1
1	PLS 852	1
1		1
1		1
1		1

Description of corner evidence found:
None

Description of monument and accessories I established to perpetuate the original location of this corner:

I set a 2 1/2" x 30" aluminum pipe 26" in the ground. I stamped the cap as shown in the diagram above. A 30" mound of stone is placed around the monument.

I set the following new witness trees:

A 9" dbh Douglas Fir bears N70°24'W, 21.6', scribed C 1/4 S30 BT.

A 6" dbh White Fir bears N79°35'E, 41.7', scribed C 1/4 S30 BT.


A 14" dbh White Fir bears S51°33'E, 85.0', scribed C 1/4 S30 BT.

A 8" dbh Alpine Fir bears S13°18'E, 20.0', scribed C 1/4 S30 BT.


The bearings are based on traverse control stations and are true.

A brass washer stamped ORLS852 and WALS 13922 is attached between the letters B and T with a brass screw on each new tree. All the BT's have Bearing Tree and Land Survey Monument signs attached. A red stripe is painted around each tree at chest height.

This work was done August 16, 1995 and witnessed by Stephen Haddock and Rob Carter, owner of adjacent land.



David L. Haddock



Office of Survey County of Umatilla
 State of Oregon, I hereby certify that the within instrument was filed
 in this office for record on the 23rd day of October, 1995.
 _____ by _____
 (COUNTY OFFICIAL) (DEPUTY)

RECEIVED BY
 Umatilla County Survey
 Date 10-95
 Rec'd By KK
 No. 95-179-B