


CERTIFIED RECORD OF LAND CORNER MONUMENTATION

INDEX: T-7

History of original corner establishment:

A. Corner not established by GLO



Description of corner evidence found:

B. MONUMENT FOUND:

none

Description of monument and accessories established to perpetuate the original location of this corner:

C. I set in place a 2.5 inch dia. by 30 inch long aluminum monument 24 inches in the ground. No stones available.

I mark the cap:

T4N R38E WM
C1/4
S29 +
1989
STRYKER PLS 2060

NEW ACCESSORIES ESTABLISHED with magnetic declination of 21 deg. East

8" true fir bears N46E at 11.8 ft scribed "C 1/4 S29 RT"
10" true fir bears S8E at 33.7 ft scribed "C 1/4 S29 RT"

Painted red band around each bearing tree.
Placed brass washer marked "PLS 2060" at base of blaze on each new RT
Placed USDA Forest Service metal signs 54-3 (RT) and 54-4 (ATTENTION) on each bearing tree.
Placed 54-9 (L.S.M) and 54-2 (PROPERTY BOUNDARY) on steel fence post set 5 feet north of corner.

Office of Survey Dept County of Umatilla
State of OR I hereby certify that the within instrument was filed in this office
for record on the 6th day of November 1989
David H. Kaumbien by Kathleen K. Ambrey
(COUNTY OFFICIAL) (DEPUTY)

Form R6-7100-57 (9/71)

RECEIVED BY
Umatilla County Surveyor
Date 11-89
Rec'd by KA
No. 89-107-B

REGISTERED
PROFESSIONAL
LAND SURVEYOR
Edwin A. Stryker
OREGON
JULY 15, 1983
EDWIN A. STRYKER
2060