

USDA-FOREST SERVICE

INDEX  
 FILE NO. U-2 CORNER RECORD (SEARCH)  
 (Ref. FSM 7151.4)  
 T. 4 N R. 38 E R.D. Walla Walla County Umatilla Tract or Survey No. \_\_\_\_\_ Cor. No. \_\_\_\_\_  
 Merid. Willamette N.F. UMATILLA State Oregon \_\_\_\_\_ 1

CORNER DIAGRAM T4N R38E 1 DESCRIBE CORNER MONUMENT FOUND  
 1 1 1 Corner not previously set.  
 1 SW---S30 1  
 N 16 1  
 1 1995 1----- 2  
 1 PLS 852 1 DESCRIBE BEARING TREES OR OTHER OFFICIAL ACCESSORIES FOUND  
 ----- 1 Corner not previously set.

PHOTO IDENTIFICATION DATA 1  
 Photo No. \_\_\_\_\_ 1  
 Filed At. \_\_\_\_\_ 1  
 Object Ident. \_\_\_\_\_ 1  
 Ident. By \_\_\_\_\_ 1  
 Signature 71 3

PLANE COORDINATE POSITION DATA 1 DESCRIBE CORNER LOCATION RELATIVE TO NEAR-BY FEATURES, ALSO HOW TO REACH CORNER  
 State \_\_\_\_\_ Zone \_\_\_\_\_ 1 The corner may be reached by traveling Highway 204 west from the Tollgate Store 1 mile to  
 X \_\_\_\_\_ 1 the point where the Highway passes under a high voltage power line. Follow the northerly edge  
 Y \_\_\_\_\_ 1 of the power line clearing about 300' east to where it crosses the posted Forest Service  
 Estab. By \_\_\_\_\_ 1 boundary line. Follow this posted line south 60' to the corner.  
 Agency 81 4

Signature \_\_\_\_\_ Title \_\_\_\_\_ Division \_\_\_\_\_ Headquarters \_\_\_\_\_ Date FS-7100-52 (3/68)  
 Surveyor \_\_\_\_\_ Pendleton, OR 9-04-95 5

CORNER RECORD (PERPETUATION)

-----  
MONUMENT : DESCRIBE NEW MONUMENT SET, OR WORK DONE TO PRESERVE EXISTING MONUMENT

Set a 2 1/2" X 30" aluminum pipe and cap 26" into the ground with a 24" collar of stone. Stamped the cap as shown in the corner diagram on the opposite side of this card.

9

-----  
ACCESSORIES : DESCRIBE NEW BT'S WITNESS OBJECTS ETC. ESTABLISHED, OR WORK DONE TO PRESERVE EXISTING EVIDENCE

Set new bearing trees.

A 24" dbh Engleman Spruce bears N47°23'W, 70.2' scribed SW 1/16 S30 BT.

A 14" dbh White Fir bears N16°12'E, 55.1' scribed SW 1/16 S30 BT.

A brass washer stamped ORLS 852 and WALS 13922 is nailed between the letters B and T on each tree with a brass screw. All the BT's have Bearing Tree and Land Survey Monument signs attached. A red band is painted around each tree at chest height.

10

-----  
Work Done By David L. Haddock Title Land Surveyor Date 8-15-95 State Registration No. \_\_\_\_\_  
Certified Cor. Record Prepared? x Yes No Filed At: Umatilla County Surveyor Date 9-95 or Agency PLS 852 11

-----  
REMARKS

12

-----  
Index File No. U-2 T. 4 N. R. 38 E. M. Willamette Tract or Surv. No. \_\_\_\_\_ Cor. \_\_\_\_\_ 13  
GPO : 1984 O - 439-095