

USDA-FOREST SERVICE

INDEX
 FILE NO. U-3
 T. 4 N R. 38 E R.D. Walla Walla County Umatilla
 Merid. Willamette N.F. UMATILLA State Oregon

CORNER RECORD (SEARCH)
 (Ref. FSN 7151.4)

Tract or
 Survey No. _____
 Cor. No. _____

CORNER DIAGRAM T4N R38E 1 DESCRIBE CORNER MONUMENT FOUND
 1 CS1/16 1 Corner not previously set.
 1 S30 1
 N 1995 1
 1 PLS 852 1
 1 DESCRIBE BEARING TREES OR OTHER OFFICIAL ACCESSORIES FOUND
 1 Corner not previously set.

PHOTO IDENTIFICATION DATA 1
 Photo No. _____ 1
 Filed At. _____ 1
 Object Ident. _____ 1
 Ident. By _____ 1
 Signature 71 1

PLANE COORDINATE POSITION DATA 1 DESCRIBE CORNER LOCATION RELATIVE TO NEAR-BY FEATURES, ALSO HOW TO REACH CORNER
 State _____ Zone _____ 1 The corner may be reached by traveling from the McIntyre Road from the Tollgate Store
 X _____ 1 0.5 mile to a Forest Boundary sign mounted on a wood post on the west edge of the road.
 Y _____ 1 The corner is located 200' east of this point.
 Estab. By _____ 1
 Agency 81 1

Signature _____ Title _____ Division _____ Headquarters _____ Date FS-7100-52 (3/68)
 Surveyor _____ Pendleton, OR 9-04-95

CORNER RECORD (PERPETUATION)

MONUMENT : DESCRIBE NEW MONUMENT SET, OR WORK DONE TO PRESERVE EXISTING MONUMENT

Set a 2 1/2" X 30" aluminum pipe and cap 26" into the ground with a 30" collar of stone. Stamped the cap as shown in the corner diagram on the opposite side of this card.

9

ACCESSORIES : DESCRIBE NEW BT'S WITNESS OBJECTS ETC. ESTABLISHED, OR WORK DONE TO PRESERVE EXISTING EVIDENCE

Set new bearing trees.

A 18" dbh White Fir bears S37°40'W, 13.1' scribed CS 1/16 S30 BT.

A 19" dbh Engleman Spruce bears N19°18'W, 11.4' scribed CS 1/16 S30 BT.

A brass washer stamped ORLS 852 and WAL5 13922 is nailed between the letters B and T on each tree with a brass screw. All the BT's have Bearing Tree and Land Survey Monument signs attached. A red band is painted around each tree at chest height.

10

Work Done By. <u>David L. Haddock</u>	Title <u>Land Surveyor</u>	Date <u>8-18-95</u>	State Registration No.
Certified Cor. Record Prepared? <u>x</u>	<u>Yes</u>	<u>No</u>	or Agency <u>PLS 852</u>
		Filed At: <u>Umatilla County Surveyor</u>	Date <u>9-95</u>

11

REMARKS

12

Index File No. U-3 T. 4 N. R. 38 E. M. Willamette Tract or Surv. No. Cor.

13