


CERTIFIED RECORD OF LAND CORNER MONUMENTATION

V- 12

History of original corner establishment:

James D. Hanley originally established this corner in July 1976 under contract # 004971N Set a 2" by 30" iron Pipe with a 2 1/2" Brass cap 2" below the surface (and a steel fence post 2 ft. west) from which:
a 11" spruce bears N 30° W 24.3 feet
a 14" spruce bears S 44° W 33.3 feet



Description of corner evidence found:

Found 2" Iron Pipe with 2 1/2" Brass Cap stamped as diagram 2" below surface. from which:
a 11" spruce snag bears S 30° W 24.3 ft. some scribe marks visible
a 14" spruce bears S 44° W 33.3 ft. E 1/16 S 33 BT visible on blaze.
A steel fence post with no signs is 0.5 ft. West.

Description of monument and accessories established to perpetuate the original location of this corner:

Attached a USFS 54-9 sign to fence post
New bearing tree
a 8" spruce bears N 89° E 30.6 feet Scribed E 1/16 S 28 BT
I nailed Alum. tag stamped 951 to bottom of blaze and painted blaze red. Painted red band around BT's and nailed 54-3 and 54-9 signs to them.

I hereby certify the above corner location was perpetuated as herein described in July, 1985.

Jud Coppock Jud Coppock, Witness

REGISTERED PROFESSIONAL LAND SURVEYOR

G. Dennis Edwards

OREGON JULY 18, 1971 G. DENNIS EDWARDS 951

Office of..... County of.....
State of....., I hereby certify that the within instrument was filed in this office for record on the..... day of....., 19.....
..... by
(COUNTY OFFICIAL) (DEPUTY)

Form R6-7100-57 (9/71)

RECEIVED BY
Umatilla County Surveyor
Date 8-6-85
Rec'd By KA
No. 85-99-R
95-C