


V-14

CERTIFIED RECORD OF LAND CORNER MONUMENTATION

History of original corner establishment:

Corner established this survey.



Description of corner evidence found:

Description of monument and accessories I established to perpetuate the original location of this corner

Set a 2 1/2" brass cap on a 2" iron pipe 31" long 4" above the ground with a 6' steel fence post 3' west with sign 54-4 attached.

from which:

A fir 10" diam. bears S 29° E., 29.0 ft. dist. marked W1/16 S34 BT
A spruce 12" diam. bears N 76° W., 34.75 ft. dist. marked W1/16 S 27 BT

Each BT has a sign 54-3 attached 6" below a band of red paint and has a brass washer marked RPE 2808 nailed flush with BT blaze.



Office of Surveyor County of Umatilla
 State of Oregon, I hereby certify that the within instrument was filed in this office
 for record on the 26 day of Aug., 1976.
 _____ by _____
 (COUNTY OFFICIAL) (DEPUTY)