

USDA-FOREST SERVICE

Index

File No. V-16

CORNER RECORD (SEARCH)

(Ref. FSM 7151.4)

Tract or

Survey No. \_\_\_\_\_

Cor.

No. \_\_\_\_\_

T 4N R. 38E

R.D. Walla Walla County Umatilla

Merid. Will

N.F. Umatilla State OR

CORNER DIAGRAM

↑  
N  
T 4N R 38E  
E 1 5 27  
10 5 34  
RPE 2808  
1976

DESCRIBE CORNER MONUMENT FOUND

Found 2" Iron pipe with B.C. stamped as diagram in mound of stone a steel fence post 3 ft. East

DESCRIBE BEARING TREES OR OTHER OFFICIAL ACCESSORIES FOUND

A 13" Fir bears S 23° W 165 ft.  
1/16 534 BT visible

PHOTO IDENTIFICATION DATA

Photo No. \_\_\_\_\_

Filed At. \_\_\_\_\_

Object Ident. \_\_\_\_\_

Ident. By \_\_\_\_\_

Signature

PLANE COORDINATE POSITION DATA

State \_\_\_\_\_ Zone \_\_\_\_\_

X \_\_\_\_\_

Y \_\_\_\_\_

Estab. By \_\_\_\_\_

Agency

DESCRIBE CORNER LOCATION RELATIVE TO NEAR-BY FEATURES, ALSO HOW TO REACH CORNER

From Jet Rd. #64 with #6403 go Nly on Rd #6403 0.1 mile  
Corner lies 800'± West of Rd.  
Corner lies 40'± south of creek bed.

Signature  
M. Dennis Edward

Title  
CS 951

Division

Headquarters  
Hermiston

Date

7/19/05

7100-52 (3.68)

**CORNER RECORD (PERPETUATION)**

**MONUMENT: DESCRIBE NEW MONUMENT SET, OR WORK DONE TO PRESERVE EXISTING MONUMENT**

Attached 54-9 signs to fence post

**ACCESSORIES: DESCRIBE NEW BT'S WITNESS OBJECTS ETC. ESTABLISHED, OR WORK DONE TO PRESERVE EXISTING EVIDENCE**

New BT

A 15" fir bears N 13° E 18.4 ft. scribed E 1/16 S 27 BT.

Note: trunk is bowed, bearing & dist taken to center of tree at center of blaze.

I nailed an alum. tag # 951 to Btm Blaze & Painted Blazes Red.

Painted Red Band around BT's & attached 54-3 & 54-9 signs ON-10

Work Done By G. D. Edwards Title LS Date 7/19/85 State Registration No. OR 951  
or Agency

Certified Cor. Record Prepared?  Yes  No Filed At: Pendleton, OR Date 7 / 195 11


REMARKS

Index  
 File No. V 16  
 T 4 N R. 38 E  
 Merid. Willamette

**CORNER RECORD (SEARCH)**

(Ref. FSM 7151.4)

Tract or Survey No. \_\_\_\_\_ Cor. No. V 16  
 R.D. Walla Walla County Umatilla  
 N.F. Umatilla State Oregon



DESCRIBE CORNER MONUMENT FOUND

NONE

DESCRIBE BEARING TREES OR OTHER OFFICIAL ACCESSORIES FOUND

NONE

PHOTO IDENTIFICATION DATA

Photo No. \_\_\_\_\_  
 Filed At. \_\_\_\_\_  
 Object Ident. \_\_\_\_\_  
 Ident. By \_\_\_\_\_  
 Signature \_\_\_\_\_

DESCRIBE CORNER LOCATION RELATIVE TO NEAR-BY FEATURES, ALSO HOW TO REACH CORNER

From corner to secs 26, 27, 34 & 35, the 1/16 corner is 1320 feet west—800 ft. west of Skyline road to Dayton, Washington.

PLANE COORDINATE POSITION DATA

State \_\_\_\_\_ Zone \_\_\_\_\_  
 X \_\_\_\_\_  
 Y \_\_\_\_\_  
 Estab. By \_\_\_\_\_  
 Agency \_\_\_\_\_

Signature: James D. Hanley Title ORPE 2808 Division \_\_\_\_\_ Headquarters \_\_\_\_\_ Date 7/13/76 7100-52 (3/68)

CORNER RECORD (PERPETUATION)

MONUMENT: DESCRIBE NEW MONUMENT SET, OR WORK DONE TO PRESERVE EXISTING MONUMENT

Set a 2 1/2" brass cap on a 2" iron pipe 31" long 6" above the ground in earth and rock mound with signs 54-4 and 54-2 attached.

9

ACCESSORIES : DESCRIBE NEW BT'S WITNESS OBJECTS ETC. ESTABLISHED, OR WORK DONE TO PRESERVE EXISTING EVIDENCE

A fir 13" diam. bears S 23° W., 16.5 ft. dist marked 1/16 S 3/4 BT with a sign 54-3 attached 6" below a band of red paint and a brass washer marked RPE 2808 nailed flush with BT blaze.

No available trees in sec. 27

10

Work Done By James D. Hanley Title Engineer Date 7/13/76 State Registration No. ORPE 2808  
Certified Cor. Record Prepared? Yes  Filed At: Pendleton, Oregon Date 8/ /76

11

REMARKS

Corner is on west face of hill approx 200 ft. below NE corner to sec. 34.

12

Index File No. V 16 T. 4 N. R. 38 E. M. W Tract or Surv. No. Cor. 13