

CERTIFIED RECORD OF LAND CORNER MONUMENTATION

History of original corner establishment:

Index: V-3

One Quarter Corner, Secs. 30 & 31, T4N, R38E, WM.			
Corner originally set by Frank Campbell in contract	1	DIAGRAM	1
468 dated 1883. His record reads:	1		1
Set a basalt stone 16x12x5 ins 11 ins in ground for	1		1
1/4 sec cor marked 1/4 on N face from which a fir	1	1 S30	1
24 ins dia bears S16°W 230 lks dist marked 1/4 S BT.	1	- ---	1
A fir 20 ins dia bears N42°W 300 lks dist marked 1/4 S1	1	4 S31	1
The corner was remonumented in 1939 by Gould under	1	1939	1
special instructions. His record reads:	1		1
At point for cor. Set an iron post, 3 ft. long, 1 in.	1		1
diam., 27 ins. in the ground, with the original stone	1		1
deposited at the base, for 1/4 sec. cor., with brass	1		1
cap marked(see diagram) from which a rotten and fallen			
fir, bears N.42°W., 300 lks. dist., marks rotted off. (Old B. T.)			
A rotten and fallen fir, bears S.16°W., 230 lks. dist., marks rotted			
off. (Old B. T.) A double Tamarack, 9 ins. diam., bears N.50°W., 285			
lks. dist., marked 1/4 S 30 B T. (New B. T.) A spruce, 16 ins. diam.,			
bears S.22°E., 191 lks. dist., marked 1/4 S 31 B T. (New B. T.)			

Description of corner evidence found:

Found 2 1/2" GLO brass cap in good condition in a mound of stone. Found 16" dbh double Western Larch stump with healed blaze N50°W, 188.1'. No evidence of other BT's found.

Description of monument and accessories I established to perpetuate the original location of this corner:

I set the following new witness trees:

A 14" dbh Western Larch bears S14°46'E, 142.9', scribed 1/4 S31 BT.

A 7" dbh White Fir bears S16°57'W, 96.1', scribed 1/4 S31 BT.

A 5/8" rebar with 2" Al cap bears N45°37'E, 103.1', stamped

BO Cor S45°37'W 103.1'.

A short power pole with plate UECA 4N E 31490 bears N56°47'W, 4.6' scribed 1/4 S30 BO.

The bearings are based on traverse control stations and are true.

A brass washer stamped ORLS852 and WALS 13922 is attached between the letters B and T with a brass screw on each new tree. All the BT's have Bearing Tree and Land Survey Monument signs attached. A red stripe is painted around each tree at chest height.

This work was done August 17, 1995 and witnessed by Stephen Haddock.

Office of Survey County of Umatilla
 State of OREGON, I hereby certify that the within instrument was filed
 in this office for record on the 23rd day of October, 1995.
 _____ by _____
 (COUNTY OFFICIAL) (DEPUTY)

REGISTERED
PROFESSIONAL
LAND SURVEYOR

David L. Haddock

OREGON
JULY 12, 1988
DAVID L. HADDOCK
852

RECEIVED BY
 Umatilla County Survey
 Date 10-95
 Rec'd by JK
 No. 95-179-B