


CERTIFIED RECORD OF LAND CORNER MONUMENTATION

History of original corner establishment:

Corner originally established by Frank W. Campbell in 1883 under General Land Office contract number 468. Corner was subsequently reestablished by Otis S. Gould in July 1939 for the U.S. General Land Office. Surveyor Gould record states:

At proportionate measurement set an iron post 3 feet long, 1 inch in diameter, 27 inches in the ground for 1/4 section corner, with brass cap marked (as shown below) from which:



- A Pine 9 inches diameter bears N15°E, 13 lks dist marked 1/4 S29 BT
- A Pine 12 inches diameter bears South 22 lks dist marked 1/4 S32 BT

No record of subsequent remonumentation found in county records
Description of corner evidence found:

Found 1 inch galvanized iron pipe with 2 inch brass cap marked as shown below, firmly set 3 inches above ground

Found steel fencepost approximately 5 feet East with 54-2 and 54-4 signs attached

Found a 12 inch diameter Lodgepole Pine N20°E (record N15°E) 8.0 feet (record 13 lks) Blaze evident and partial scribes visible

Description of monument and accessories I established to perpetuate the original location of this corner:

New BTs

A 15 inch diameter Spruce bears S15°E, 26.8 feet marked 1/4 S32 on a single blaze

New tree taken July 12, 1985

REGISTERED PROFESSIONAL LAND SURVEYOR

Gregory T. Blackman

OREGON JULY 13, 1973 GREGORY T. BLACKMAN 991



I used a steel tape and magnetic compass in the establishment of this accessory. I used 20° East magnetic declination and the distance is to the center of the tree. I set a brass washer marked OPLS 991 by the BT blaze. I painted a 6 inch red band around all BTs and attached 54-3 and 54-4 signs

Office of..... County of.....
State of....., I hereby certify that the within instrument was filed in this office for record on the..... day of....., 19.....
..... by
(COUNTY OFFICIAL) (DEPUTY)

Form R6-7100-57 (9/71)

RECEIVED BY
Umatilla County Surveyor
Date 7-24-85
Rec'd By KA
No. 85-82-R