


T 4 N R 38 E

History of original corner establishment:


None



X-14

Description of corner evidence found:

Found 1/2" iron pipe N 34° 00' 31" W 22.00 feet from corner.
no record



Description of monument and accessories I established to perpetuate the original location of this corner:

Set a 2" x 30" iron pipe 29" in ground with brass cap stamped from which:

a 16" fir bears N 60° E 9.5 feet scribed CW 1/16 S 34 BT
a 10" fir bears S 15° E 11.4 ft. scribed CW 1/16 S 34 BT

I nailed alum. tags stamped 951 to bottom blazes and painted blazes red. Painted red band around BT's and nailed USFS signs 54-3 and 54-9 to them.

Drove a steel fence post 3 ft east and attached 54-9 sign.

I hereby certify the above corner location was perpetuated as herein described in July 1985.

Jud Coppock
Jud Coppock, Witness

REGISTERED
PROFESSIONAL
LAND SURVEYOR

G. Dennis Edwards

OREGON
JULY 18, 1971
G. DENNIS EDWARDS
951

Office of..... County of.....
State of....., I hereby certify that the within instrument was filed in this office
for record on the..... day of....., 19.....
..... by

(COUNTY OFFICIAL)

(DEPUTY)

RECEIVED BY

Umatilla County Surveyor

Date 8-6-85

Rec'd By KA

No. 85-107-R

95-C

Form R6-7100-57 (9/71)