


CERTIFIED RECORD OF LAND CORNER MONUMENTATION

X-5

History of original corner establishment:

Corner established in 1883 by Frank W. Campbell under GLO contract number 468. Corner was subsequently reestablished by Otis S. Gould for the U.S. General Land Office in July, 1939. Surveyor Gould record states:



At proportionate measurement set an iron post 3 feet long 1 inch in diameter 27 '' in the ground for 1/4 section corner, with brass cap marked (shown below);

A Fir 11 inches diameter bears S63°E, 6 lks dist marked 1/4 S 32 BT
A Fir 22 inches diameter bears N71°W, 8 lks dist marked 1/4 S 31 BT

No record of subsequent remonumentation found in county records
Description of corner evidence found:

Found brass cap as described above.

Found 13 inch diameter Fir dead and down, scribes visible, S73°E (record S63°E) 3.0 ft.

Found Fir stump, rotted, scribes visible, N65°W, (record N71°W) 4.6 feet

Description of monument and accessories established to perpetuate the original location of this corner:

New BTs

A 24 inch diameter Spruce bears N14°E 58.8 feet marked 1/4 S32 BT on a single blaze
A 16 inch diameter Spruce bears N52°W, 105.0 feet marked 1/4 S31 BT on a single blaze

I set a steel fencepost approximately 5 feet North with 54-4 sign attached

Trees taken July 10, 1985

Witnesses: Rick Robinson, Ray Crope and Stratton French



REGISTERED PROFESSIONAL LAND SURVEYOR

Gregory T. Blackman

OREGON JULY 13, 1973 GREGORY T. BLACKMAN 991

I used a steel tape and magnetic compass in the establishment of these accessories. I used 20° East magnetic declination and the distances are to the center of the trees. I set a brass washer marked OPLS 991 by the BT blaze. I painted a 6 inch red band around all BTs and attached 54-3 and 54-4 signs.

Office of..... County of.....
State of..... I hereby certify that the within instrument was filed in this office for record on the..... day of....., 19.....
(COUNTY OFFICIAL) by (DEPUTY)

Form R6-7100-57 (9/71)

RECEIVED BY
Umatilla County Surveyor
Date 7-24-85
Rec'd By SA
No. 85-87-R
181-B