

CERTIFIED RECORD OF LAND CORNER MONUMENTATION

History of original corner establishment:

Index: Z-7

South Quarter corner Sec. 32, T.4N., R.38E., W.M.
 Original corner was set by Pershin in June 1879.
 His notes record:
 Set Pine post for 1/4 sec. cor. :
 A Pine 10 ins. di. brs. N.15°E. 12 lks. dist
 A Pine 15 ins. di. brs. S.50°E. 13 lks. dist

1	DIAGRAM	1
1		1
1	1	1
1	- S 32	1
1	4	1
1		1
1		1
1	1939	1
1		1
1		1

In 1939, the GLO remonumented this corner.
 Their record reads:
 Set an iron post, 3 ft. long, 1 ins. diam., 27 ins.
 in the ground, with brass cap marked (diagram)
 from which

A dead pine, 15 ins. diam., brs. N.15°E., 12 lks. dist., marked 1/4 S BT.
 A Spruce, 16 ins. diam., brs. N.30°W., 30 lks. dist., marked 1/4S BT.


Description of corner evidence found:

Found the iron pipe as described with brass cap stamped as shown in the diagram. From this monument:
 A 16" dbh dead and down Spruce, N30°W, 20' with visible BT scribe.


Description of monument and accessories I established to perpetuate the original location of this corner:

The bearings were based on the surveyed bearing between this 1/4 section corner and the corner to the west as recorded by RPE 2808 in a filed Umatilla County survey. I set the following new witness trees:
 A 25" dbh Engleman Spruce bears N57°15'W, 22.5' scribed 1/4 S32 BT;
 A 17" dbh Engleman Spruce bears S75°23'W, 44.5' scribed 1/4 S5 BT.
 A 14" dbh Engleman Spruce bears N81°47'E, 37.5' scribed 1/4 S32 BT.
 A 21" dbh Engleman Spruce bears S78°50'E, 19.3' scribed 1/4 S5 BT.
 An aluminum washer stamped RLS 852 is nailed between the letters B and T on each new tree. All four living trees have LSM and BT signs attached. Painted 6" red bands around all four living trees and painted the scribe blazes red.

This work was done July 11, 1992.



David L. Haddock



Office of _____ County of _____
 State of _____, I hereby certify that the within instrument was filed
 in this office for record on the _____ day of _____, 19____.
 _____ by _____
 (COUNTY OFFICIAL) (DEPUTY)

Form R6-7100-57 (9/71)

RECEIVED BY
 Umatilla County Surveyor
 Date 8-92
 Rec'd By KE
 No. 92-95-R