


**CERTIFIED RECORD OF LAND CORNER MONUMENTATION**

E - 15  
DIAGRAM

**History of original corner establishment:**

The original corner was established by George S. Pershin on June 16, 1882, under GLO contract No. 430, as follows:

Set a basalt stone, 15" x 8" x 5", 10" in ground on level ground for the 1/4 section corner to sections 3 and 10 marked "1/4" on the north face. No trees. Raised a mound of stones alongside in lieu of pits.



**Original corner evidence recovered:**

Found the original corner stone loosely set in a mound of stones. The corner stone is 14" x 10" x 6" and has faint marks on one face. A Bureau of Land Management "Location Sign", dated 6 - 10 - 77, is under the base of the corner stone.

**Monument and accessories established to perpetuate the original position of this corner:**

In place of the corner stone, I set a 1" x 18" flared, galvanized iron pipe 16" into the ground to bedrock. I place the corner stone and the Location Sign along the north side of the pipe and build a mound of stones around the pipe. A 2 1/2" brass cap attached to the top of the pipe is marked as shown in the diagram above, from which:

A 5/8" x 24" iron rod set 23" into the ground with a 3/4" brass washer, marked "PLS 1636 NE", attached at ground level, bears N60° E, 118.7 feet.

A 5/8" x 24" iron rod set 23" into the ground with a 3/4" brass washer, marked "PLS 1636 SE", attached at ground level, bears S51° 30' E, 183.4 feet.

A 5/8" x 18" iron rod set 16" into the ground with a 3/4" brass washer, marked "PLS 1636 SW", attached at ground level, bears S43° W, 114.3 feet. This reference is at the base of an 18" high boulder.

A 5/8" x 24" iron rod set 23" into the ground with a 3/4" brass washer, marked "PLS 1636 NW", attached at ground level, bears N43° 30' W, 135.2 feet.

I hereby certify the above corner point was perpetuated as hereon described on April 7, 2004. Magnetic declination set in compass: 18° E.  
NAD '83 UTM Zone 11 position: 5011980N, 337097E (plus or minus two meters).



Renews June 30, 2005

Recorded at the office of County Surveyor, County of Umatilla, State of Oregon, on:

RECEIVED BY  
Umatilla County Surveyor  
Date 5-04  
Rec'd By KK  
No. 04-93-B