

CERTIFIED RECORD OF LAND CORNER MONUMENTATION

History of original corner establishment:

Corner established in 1882 by George S. Pershin under General Land Office Contract No. 430.

Surveyor General's records state:

Set a basalt stone 15x10x7 ins. 10 ins. in the ground on steep N.W. slope for cor. to Sec. 1, 2, 11 and 12 marked with 5 notches on South and 1 notch on East edges; descent about 300 ft.

A pine 10 ins. dia. brs. N26°E, 48 lks. dist. marked T4S R30E S 1 BT.

A fir 12" ins. dia. brs. S44°E, 60 lks. dist. marked T4S R30E S 12 BT.

A fir 14 ins. dia. brs. S72°W, 108 lks. dist. marked T4S R30E S 11 BT.

Description of corner evidence found:

A pine 16 ins. dia. brs. N61°W, 38 lks. dist. marked T4S R30E S 2 BT.

Description of corner evidence found:

Original stone not found; corner on a steep N.W. slope, corner stone has apparently eroded out and rolled down the slope. A fire has gone through the area some 40-50 years ago.

Found 16 in. pine, dead and down, with BT scribing visible. Tree has rolled down the slope. There has been no substantial growth of the tree since it was scribed. It is determined that this is the Sec. 2 BT; therefore corner is positioned at record call from approx. original position of the tree. No other bearing trees conclusive, due to fire.

Description of monument and accessories established to perpetuate the original location of this corner:

Set 3"x30" galv. iron pipe with 3" brass cap stamped as shown on the diagram. Set 20 inches in the ground.

From which:

A fir 12 inches dia. bears N9°E, 36.2 ft. scribed T4S R30E S1 BT.

A pine 10 inches dia. bears S14°E, 30.3 ft. scribed T4S R30E S 12 BT.

A fir 15 inches dia. bears S39°W, 47.2 ft. scribed T4S R30E S 11 BT.

A fir 8 inches dia. bears N56°W, 27.6 ft. scribed X BT.

Set steel post with warning sign 4 ft. North from corner.

Nailed bearing tree signs and brass washers stamped PLS 848 to each tree.

Painted a red band around each tree.

I hereby certify that the above corner monument was reestablished as herein described on 8/11/81.

REGISTERED
PROFESSIONAL
LAND SURVEYOR

Douglas M. Ferguson

OREGON
JULY 12, 1968
DOUGLAS M. FERGUSON
848

Witnesses: D. Mitchell Ferguson


Mike Woodward

Office of... Co. Surveyor..... County of... Umatilla

State of... Oregon..... I hereby certify that the within instrument was filed in this office

for record on the 11th day of January, 1982

..... Douglas M. Ferguson by Betty Shedd
(COUNTY OFFICIAL) (DEPUTY)



E-21

CERTIFIED RECORD OF LAND CORNER MONUMENTATION

History of original corner establishment:

Corner established in 1882 by George S. Pershin under General Land Office Contract No. 430. Surveyor General's records state:

Set a basalt stone 15x10x7 ins. 10 ins. in the ground on steep N.W. slope for cor. to Sec. 1, 2, 11 and 12 marked with 5 notches on South and 1 notch on East edges; descent about 300 ft.

A pine 10 ins. dia. brs. N26°E, 48 lks. dist. marked T4S R30E S 1 BT.

A fir 12 ins. dia. brs. S44°E, 60 lks. dist. marked T4S R30E S 12 BT.


A fir 14 ins. dia. brs. S72°W, 108 lks. dist. marked T4S R30E S 11 BT.

A pipe 16 ins. dia. brs. N61°W, 38 lks. dist. marked T4S R30E S 2 BT.

Description of corner evidence found:

Original stone not found; corner on a steep N.W. slope, corner stone has apparently eroded out and rolled down the slope. A fire has gone through the area some 40-50 years ago.

Found 16 in. pine, dead and down, with BT scribing visible. Tree has rolled down the slope. There has been no substantial growth of the tree since it was scribed. It is determined that this is the Sec. 2 BT; therefore corner is positioned at record call from original position of the tree. No other bearing trees conclusive, due to fire.



E-21

Description of monument and accessories | established to perpetuate the original location of this corner:

Set 3"x30" galv. iron pipe with 3" brass cap stamped as shown on the diagram. Set 20 inches in the ground.

From which:

A fir 12 inches dia. bears N9°E, 36.2 ft. scribed T4S R30E S 1 BT.

A pine 10 inches dia. bears S14°E, 30.3 ft. scribed T4S R30E S 12 BT.

A fir 15 inches dia. bears S39°W, 47.2 ft. scribed T4S R30E S 11 BT.

A fir 8 inches dia. bears N56°W, 27.6 ft. scribed X BT.

Set steel post with warning sign 4 ft. North from corner.

Nailed bearing tree signs and brass washers stamped PLS 848 to each tree.

Painted a red band around each tree.

I hereby certify that the above corner monument was reestablished as herein described on 8/11/81.

REGISTERED PROFESSIONAL LAND SURVEYOR

OREGON JULY 12, 1968 DOUGLAS M. FERGUSON 848

Witnesses: D. Mitchell Ferguson

Mike Woodward

Office of... Co. Surveyor... County of... Umatilla

State of... Oregon... I hereby certify that the within instrument was filed in this office

for record on the... day of... January... 1982

David Humbern by Betty Sheth (COUNTY OFFICIAL) (DEPUTY)

82-1-B

T-2