

Index
File No. H-24

CORNER RECORD (SEARCH)
(Ref. FSM 7151.4)

Tract or
Survey No. _____ Cor.
No. _____

T T45 R. 30E

R.D. Ukiah County Umatilla

Merid. Willamette

N.F. Umatilla State Oregon

CORNER DIAGRAM

T45 R30E
SE 1/16 S 12
1981
PLS 848



DESCRIBE CORNER MONUMENT FOUND

Corner not previously established.

DESCRIBE BEARING TREES OR OTHER OFFICIAL ACCESSORIES FOUND

N/A

PHOTO IDENTIFICATION DATA

Photo No. _____
Filed At. _____
Object Ident. _____
Ident. By _____
Signature

PLANE COORDINATE POSITION DATA

State _____ Zone _____
X _____
Y _____
Estab. By _____
Agency

DESCRIBE CORNER LOCATION RELATIVE TO NEAR-BY FEATURES, ALSO HOW TO REACH CORNER

Corner is on N.E. slope at the edge
of the timber.

Signature _____ Title PLS 848 Division _____ Headquarters Mt. Vernon, OR Date 8/5/81 7100-52-(3.68)

CORNER RECORD (PERPETUATION)

MONUMENT: DESCRIBE NEW MONUMENT SET, OR WORK DONE TO PRESERVE EXISTING MONUMENT

Set 3"x30" galv. iron pipe with 3" brass cap stamped as shown on the diagram. Set pipe 18 inches in the ground and raised a mound of stone around the pipe.

From which:

ACCESSORIES : DESCRIBE NEW BT'S WITNESS OBJECTS ETC. ESTABLISHED, OR WORK DONE TO PRESERVE EXISTING EVIDENCE

A pine 16 inches dia. bears N43°W, 121.3 ft. scribed SE 1/16 S 12 BT.
 A pine 14 inches dia. bears N86°E, 30.5 ft. scribed SE 1/16 S 12 BT.
 Set steel posts with warning and boundary signs 5 ft. West and 5 ft. South from corner.
 Nailed bearing tree signs and brass washers stamped PLS 848 to each tree.

Work Done By D.M. Ferguson Title Surveyor Date 8/5/81 State Registration No. OR PLS 848
 or Agency

Verified REGISTERED Expired? Yes No Filed At Umatilla Co. Surveyor Off Date

**REGISTERED
 PROFESSIONAL
 LAND SURVEYOR**

REMARKS

Witnesses to above corner:

D. Mitchell Ferguson
 Mike Woodward

**OREGON
 JULY 12, 1968
 DOUGLAS M. FERGUSON
 848**