


CERTIFIED RECORD OF LAND CORNER MONUMENTATION

History of original corner establishment:

Corner established in 1882 by George S. Pershin under general land office contract No. 430. Surveyor General's records state:
Set basalt stone 14x8x7 ins. 10 ins. in ground on level prairie, north of and near open timber for corner to Sec. 8, 9, 16, and 17. Marked with 4 notches on S and E edges. A pine 20 ins. di. brs. S26°W, 140 lks. distance marked T4S R30E S 17 BT. No other trees near. Raised mound of stone alongside in lieu of pits.



J-9

Description of corner evidence found:

Found old mound of stone in fence corner. Mound does not appear to be a fence jack. No stones with marks visible.
Found old pine stump, burned and rotten, bears N26°W, 93 ft. from mound of stone. Due to harmony with found corners S & W, I accepted the mound of stone as the corner position.

Description of monument and accessories I established to perpetuate the original location of this corner:

Set 3"x30" galv. iron pipe with 3" brass cap stamped as shown on the diagram, set 24 inches in the ground and placed mound of stone around the pipe.
No bearing trees are available.
Set a steel post with warning sign, North alongside pipe.

I hereby certify that the above corner monument was reestablished as herein described, on 9/16/81.



Witnesses: Dave Herburger
Larry Wyllie

Office of... Umatilla Co. Surveyor County of... Umatilla
State of... Oregon... I hereby certify that the within instrument was filed in this office for record on the... 23 day of... January... 1982
... David R. ... by Betty ...
(COUNTY OFFICIAL) (DEPUTY)

82-2-B