


CERTIFIED RECORD OF LAND CORNER MONUMENTATION

History of original corner establishment:

Corner not previously established.



2-18

Description of corner evidence found:

N/A

Description of monument and accessories I established to perpetuate the original location of this corner:

Set 3" x 30" galv. iron pipe with 3" brass cap stamped as shown on the diagram, set 20" in the ground.

From which:

A fir 9 in. dia. bears N24°E, 21.4 ft. scribed CW 1/16 S 14 BT.

A fir 8 in. dia. bears S25°E, 15.3 ft. scribed CW 1/16 S 14 BT.

Set steel posts with warning and boundary signs 5 ft. West and 5 ft. North from corner.

Nailed bearing tree signs and brass washers stamped PLS 848 to each tree. Painted red band around each tree.

I hereby certify that the above corner monument was established on 7/31/81 as herein described.

REGISTERED
PROFESSIONAL
LAND SURVEYOR

[Signature]
OREGON
JULY 12, 1968
DOUGLAS M. FERGUSON
848

Witnesses:

D. Mitchell Ferguson

Mike Woodward

Office of... Co. Surveyor..... County of... Umatilla
State of... Oregon....., I hereby certify that the within instrument was filed in this office
for record on the... 7th day of... January....., 1982
... *David Rumbler*..... by... *Betty Skate*.....
(COUNTY OFFICIAL) (DEPUTY)

82-1-B

T-2