

USDA-FOREST SERVICE

Index  
File No. L-24

CORNER RECORD (SEARCH)

(Ref. FSM 7151.4)

Tract or Survey No. \_\_\_\_\_ Cor. No. \_\_\_\_\_

T 4S R. 30E

R.D. Ukiah County Umatilla

Merid. Willamette

N.F. Umatilla State Oregon

CORNER DIAGRAM

T4S R30E

E 1/16

C ——— C

S 13

1981

PLS 848



DESCRIBE CORNER MONUMENT FOUND

Corner not previously established.

DESCRIBE BEARING TREES OR OTHER OFFICIAL ACCESSORIES FOUND

N/A

PHOTO IDENTIFICATION DATA

Photo No. \_\_\_\_\_

Filed At. \_\_\_\_\_

Object Ident. \_\_\_\_\_

Ident. By \_\_\_\_\_

*Signature*

PLANE COORDINATE POSITION DATA

State \_\_\_\_\_ Zone \_\_\_\_\_

X \_\_\_\_\_

Y \_\_\_\_\_

Estab. By \_\_\_\_\_

*Agency*

DESCRIBE CORNER LOCATION RELATIVE TO NEAR-BY FEATURES, ALSO HOW TO REACH CORNER

Corner is in open timber on South slope.  
A primitive road coursing SE. NW. approx.  
1300 ft. North from corner. NE 1/16 S 13 monumented  
just North of road.

Title \_\_\_\_\_ Division \_\_\_\_\_ Headquarters \_\_\_\_\_ Date \_\_\_\_\_

PLS 848

Mt. Vernon, OR

8/6/81

7100-52-(3:68)

*Signature*

CORNER RECORD (PERPETUATION)

MONUMENT: DESCRIBE NEW MONUMENT SET, OR WORK DONE TO PRESERVE EXISTING MONUMENT

Set 3"x30" galv. iron pipe with 3" brass cap stamped as shown on the diagram. Set pipe 16 inches in the ground and raised a mound of stone around the pipe.

From which:

ACCESSORIES : DESCRIBE NEW BT'S WITNESS OBJECTS ETC. ESTABLISHED, OR WORK DONE TO PRESERVE EXISTING EVIDENCE

A pine 10 inches dia. bears N41°E, 38.5 ft. scribed CE 1/16 S 13 BT.  
A pine 9 inches dia. bears S57°E, 55.8 ft. scribed CE 1/16 S 13 BT.  
Set steel posts with warning and boundary signs 5 ft. South and 5 ft. West from corner.  
Nailed bearing tree signs and brass washers stamped PLS 848 to each tree.  
Painted a red band around each tree.

Work Done By D.M. Ferguson Title Surveyor Date 8/6/81 State Registration No. OR PLS 848  
or Agency

Certified Cor. Record Prepared Yes  No. Filed At: Umatilla Co. Surveyor Off. Date

REGISTERED  
PROFESSIONAL  
LAND SURVEYOR

*Douglas M. Ferguson*  
OREGON  
JULY 12, 1968  
DOUGLAS M. FERGUSON  
848

REMARKS

Witnesses to above corner:  
D. Mitchell Ferguson  
Mike Woodward