


CERTIFIED RECORD OF LAND CORNER MONUMENTATION

History of original corner establishment:

Corner established in 1882 by George S. Pershin under General Land Office Contract N. 430. Surveyor General's records state: Set basalt stone 14x10x6 ins. on N. slope, 10 ins. in ground for 1/4 Sec. Cor. marked 1/4 on W. face. A pine 8 in. di. brs. S38°E, 20 lks. dist. marked 1/4 S BT. A pine 10 in. di. brs. West 43 lks. dist. marked 1/4 S BT.



L-5

Description of corner evidence found:

Original stone not found.

Found remains of 10 in. pine with 1949 location poster and blaze with small US stamped in blaze. Growth rings indicate this tree was blaced about 1949. Due to logging in area, no evidence found; therefore, set corner position by proportion.

Description of monument and accessories I established to perpetuate the original location of this corner:

Set 3"x30" galv. iron pipe with 3" brass cap, stamped as shown on the diagram, set 20 inches in the ground. From which A fir 16 in. dia. bears N18°E, 9.4 ft. scribed 1/4 S 17 BT. A fir 20 in. dia. bears S52°W, 6.3 ft. scribed 1/4 S 18 BT. Set steel posts with warning and boundary signs 5 ft. East and 5 ft. South from corner. Nailed bearing tree signs and brass washers stamped PLS 848 to each tree. Painted red band around each tree.

I hereby certify that the above corner monument was reestablished as herein described, on 9/19/81.

Witnesses D. Mitchell Ferguson

Mike Woodward

REGISTERED PROFESSIONAL LAND SURVEYOR

OREGON JULY 12, 1968 DOUGLAS M. FERGUSON 848

Office of Co. Surveyor... County of Umatilla... State of Oregon... I hereby certify that the within instrument was filed in this office for record on the 23 day of January, 1982... David H. Hansen... by Betty Skaha... (COUNTY OFFICIAL) (DEPUTY)

82-2-B