


CERTIFIED RECORD OF LAND CORNER MONUMENTATION

History of original corner establishment:

Corner not previously established.



M-18

Description of corner evidence found:

N/A

Description of monument and accessories I established to perpetuate the original location of this corner:

Set 3"x30" galv. iron pipe with 3" brass cap stamped as shown on the diagram, set 25 inches in the ground.
 A 6 inch fir south alongside pipe is scribed SW 1/16 S 14.
 From which:
 A tamarack 16 in. dia. bears N50°E, 45.4 ft. scribed SW 1/16 S 14 BT.
 A fir 11 in. dia. bears S70°E, 6.0 ft. scribed SW 1/16 S 14 BT,
 Set steel posts with warning and boundary signs 5 ft. South and 5 ft. East from corner. Nailed bearing tree signs and brass washers stamped PLS 848 to each tree. Painted a red band around each tree.

I hereby certify that the above corner monument was established as herein described on 8/12/81.

Witness: D. M. Ferguson

Mike Woodward

REGISTERED
PROFESSIONAL
LAND SURVEYOR

[Signature]
 OREGON
 JULY 12, 1968
 DOUGLAS M. FERGUSON
 848

Office of... Co. SURVEYOR..... County of... Umatilla
 State of Oregon..... I hereby certify that the within instrument was filed in this office
 for record on the... 22... day of... January... 1982
 David Krumholtz..... by Betty Judd
 (COUNTY OFFICIAL) (DEPUTY)

182-01-c