


CERTIFIED RECORD OF LAND CORNER MONUMENTATION

History of original corner establishment:

Corner not previously established.



M-20

Description of corner evidence found:

N/A

Description of monument and accessories I established to perpetuate the original location of this corner:

Set 3"x30" galv. iron pipe with 3" brass cap stamped as shown on the diagram, set 12 inches in the ground and raised a mound of stone around the pipe.

From which:

A pine 12 in. dia. bears N38°E, 20.8 ft. scribed SE 1/16 S 14 BT.

A pine 17 in. dia. bears S18°E, 22.8 ft. scribed SE 1/16 S 14 BT.

Set steel posts with warning and boundary signs 5 ft. West and 5 ft.

South from corner. Nailed bearing tree signs and brass washers stamped PLS 848 to each tree.

Painted red band around each tree.

I hereby certify that the above corner monument was established as herein described on 8/12/81.

Witnesses: _____
D. Mitchell Ferguson

Mike Woodward

REGISTERED
PROFESSIONAL
LAND SURVEYOR

Douglas M. Ferguson
OREGON
JULY 12, 1968
DOUGLAS M. FERGUSON
848

Office of... Co. Surveyor..... County of... Umatilla
State of Oregon..... I hereby certify that the within instrument was filed in this office
for record on the... 1st day of... January..... 1987
..... David Rumbler..... by Betty Shatto.....
(COUNTY OFFICIAL) (DEPUTY)