


CERTIFIED RECORD OF LAND CORNER MONUMENTATION

History of original corner establishment:

Corner established in 1882 by George S. Pershin under General Land Office Contract No. 430. Surveyor General's records state: Set basalt stone 15x10x8 ins. 10 ins. in ground on N slope for 1/4 Sec. Cor. marked 1/4 on North face. No trees near, raised a mound of stone alongside in lieu of pits.



N-11

Description of corner evidence found:

No evidence found; fence construction and maintenance over the years have destroyed all traces. No bearing trees originally established. Set corner position by proportion.

Description of monument and accessories I established to perpetuate the original location of this corner:

Set 3"x30" galv. iron pipe with 3" brass cap stamped as shown on the diagram. Set pipe 12 inches in the ground and raised a mound of stone around the pipe.

No bearing trees available. Set steel posts with warning and boundary signs 5 ft. East and 5 ft. West from corner.

I hereby certify that the above corner monument was reestablished as herein described, on 9/81.

Witnesses: Dave Herburger

Dan Martin

REGISTERED
PROFESSIONAL
LAND SURVEYOR

[Signature]
OREGON
JULY 12, 1968
DOUGLAS M. FERGUSON
848

Office of Co. Surveyor County of Umatilla
Oregon
State of Oregon, I hereby certify that the within instrument was filed in this office
for record on the 17th day of January, 1982
Daniel A. Kuhnlein by Billy Stott
(COUNTY OFFICIAL) (DEPUTY)

82-002-B