


CERTIFIED RECORD OF LAND CORNER MONUMENTATION

A-21

History of original corner establishment: Corner originally established by George S. Pershin, U.S. Deputy Surveyor, under Contract No. 373, dated September 17, 1880. The original notes state that at the corner a 16" x 10" x 5" basalt stone was set on small level for corner to S1 and 2, from which:



A 32" dia Pine bears S25°E 92 lk dist.  
A 18" dia Pine bears S34°W 95 lk dist.

No record of remonumentation found.

Description of corner evidence found:

A 15" x 12" x 7" basalt stone in mound of stone from which:

A 32" dia Pine Stump bears S23½°E 62.4 ft dist to center - (old BT, visible scribing "BT").

Description of monument and accessories I established to perpetuate the original location of this corner:

Note: This corner is located 1.04 ft North of the South line of Section 34 T3S R31E.

I set a 2 1/2" brass cap on 2 1/2" x 30" l. pipe 23" in the ground with mound of stone from which:

A 11" dia Ponderosa Pine bears S23½°E 44.0 ft dist marked: T4S R31E S1 BT.

A 14" dia Ponderosa Pine bears S51°W 52.4 ft dist marked: T4S R31E S2 BT.

Blaze faces and 6" band around bearing trees are painted red. Trees tagged with 54-3 & 4 signs. New BTs have a lower blaze, scribed BT, with a brass washer stamped PLS 1106 nailed flush. Set steel fence post with 54-2 & 4 sign attached East of corner. Used steel tape and magnetic compass 19 3/4° East declination. Measured to center of BTs.

Corner monumented on October 20, 1982.


Cap marked:

Witnessed by: Leslie E. Wilson

REGISTERED PROFESSIONAL LAND SURVEYOR
---

*William R. Wells*

OREGON JULY 22, 1977 WILLIAM R. WELLS 1106
---



Office of.....County Surveyor..... County of.....Umatilla.....  
 State of.....Oregon..... I hereby certify that the within instrument was filed in this office  
 for record on the...15<sup>th</sup> day of...December... 19.82  
 ..Daniel H. Kumberson by Betty L. Shatto.....  
 (COUNTY OFFICIAL) (DEPUTY)

A-21

REC'D BY  
 Umatilla County Surveyor  
 Date \_\_\_\_\_  
 Rec'd By \_\_\_\_\_  
 No. 82-138-B