


CERTIFIED RECORD OF LAND CORNER MONUMENTATION

History of original corner establishment:

Corner not previously established.



u-25

Description of corner evidence found:

N/A

Description of monument and accessories I established to perpetuate the original location of this corner:

Set 3"x30" galv. iron pipe with 3" brass cap stamped as shown on the diagram. Set pipe 14 inches in the ground and raised a mound of stone and earth around the pipe.

From which:

A pine 10 inches dia. bears N88°W, 56.2 ft. scribed S 1/16 S 25 BT.

A pine 14 inches dia. bears N9°E, 65.5 ft. scribed S 1/16 S 30 BT.

Set steel posts with warning and boundary signs 5 ft. West and 5 ft. South from corner.

Nailed bearing tree signs and brass washers stamped PLS 848 to each tree. Painted red band around each tree.

I hereby certify that the above corner monument was established as herein described on 7/29/81.

Witnesses: _____
D. Mitchell Ferguson

Mike Woodward

REGISTERED
PROFESSIONAL
LAND SURVEYOR

[Signature]
OREGON
JULY 12, 1908
DOUGLAS M. FERGUSON
848

Office of... Co. Surveyor... County of... Umatilla
State of... Oregon... I hereby certify that the within instrument was filed in this office
for record on the... 7th day of... January... 1982
... David Krumbein... by Betty Shultz...
(COUNTY OFFICIAL) (DEPUTY)