

CERTIFIED RECORD OF LAND CORNER MONUMENTATION

V - 9
DIAGRAM

History of original corner establishment:

The original corner was established by George S. Pershin on October 27, 1880, under GLO contract No. 373, as follows:

T4S R31E
S29|S28
S32|S33
PLS 1636
1998

Set basalt stone, 26" x 18" x 10", and a post in a mound of stone on a slight south slope for the corner to sections 28, 29, 32 and 33.

Corner evidence recovered:

Found the original corner stone solidly set on the southwest edge of a large mound of stones. The corner stone is 26" x 18" x 13" and is plainly marked with four notches on the east edge and one notch on the south edge. The original post is gone.

Monument and accessories established to perpetuate the original location of this corner:

In place of the original corner stone, I set a 1" x 30" iron pipe 12" into the ground to bedrock. A 2 1/2" brass cap attached to the pipe is marked as shown in the diagram above. I place the corner stone along the northeast side of the pipe and build a mound of stones around the pipe to the cap, and over the corner stone, from which:

A 11" Ponderosa Pine scribed "T4S R31E S28 BT" on double blazes bears N82°E, 100.3 feet. There is a 3/4" brass washer, marked "PLS 1636", nailed flush to the scribed "B", a "Bearing Object" sign nailed above the blazes and a "Witness Post" sign nailed to the back of the tree.

A 5/8" x 24" iron rod set 20" into the ground with a 3/4" brass washer, marked "PLS 1636 S33", attached at ground level, bears S40°30'E, 73.9 feet.

A 5/8" x 24" iron rod set 20" into the ground with a 3/4" brass washer, marked "PLS 1636 S32", attached at ground level, bears S42°30'W, 115.1 feet.

A 5/8" x 24" iron rod set 23" into the ground with a 3/4" brass washer, marked "PLS 1636 S29", attached at ground level, bears N75°W, 72.4 feet. This corner is approximately 175 feet west of a north-south barbed-wire fence.

I hereby certify the above corner point was perpetuated as hereon described on July 9, 1998. Magnetic declination: 18° E.



Renews June 30, 1999

Recorded at the office of County Surveyor, County of Umatilla, State of Oregon, on _____, 1998.

RECEIVED BY
Umatilla County Surveyor
Date 8-98
Rec'd By AK
No. 98-161-R