

USDA-FOREST SERVICE

Index

File No. E-11

**CORNER RECORD (SEARCH)**

(Ref. FSM 7151.4)


T 4S R. 32E

Tract or Survey No. \_\_\_\_\_  
Cor. No. 1/4

R.D. Ukiah County Umatilla

Merid. Willamette N.F. Umatilla State Oregon

**CORNER DIAGRAM**



**DESCRIBE CORNER MONUMENT FOUND**

No trace of original stone found.

**DESCRIBE BEARING TREES OR OTHER OFFICIAL ACCESSORIES FOUND**

No trace of any bearing trees found.

**PHOTO IDENTIFICATION DATA**

Photo No. \_\_\_\_\_

Filed At. \_\_\_\_\_

Object Ident. \_\_\_\_\_

Ident. By \_\_\_\_\_

*Signature*

**PLANE COORDINATE POSITION DATA**

State \_\_\_\_\_ Zone \_\_\_\_\_

X \_\_\_\_\_

Y \_\_\_\_\_

Estab. By \_\_\_\_\_

*Agency*

**DESCRIBE CORNER LOCATION RELATIVE TO NEAR-BY FEATURES, ALSO HOW TO REACH CORNER**

Corner lies on a slight southeast slope about 150 ft. east of a small clearing with a small pond in it.

*Signature*

*Signature*

Title  
PLS

Division  
1294

Headquarters

Date  
12/9/80

7100-52 (3. 68)

**CORNER RECORD (PERPETUATION)**

---

**MONUMENT: DESCRIBE NEW MONUMENT SET, OR WORK DONE TO PRESERVE EXISTING MONUMENT**

Set  $2\frac{1}{2}$ "x30" galvanized pipe with brass cap marked:  
Pipe is set 24" in ground. Mound of stone to cap.

T4S R32E  
S4  
1/4 —+—  
S9  
1977  
OR PLS 1051

---

**ACCESSORIES : DESCRIBE NEW BT's WITNESS OBJECTS ETC. ESTABLISHED, OR WORK DONE TO PRESERVE EXISTING EVIDENCE**

A Fir 16" in dia. bears N18<sup>0</sup>E, 81.0 ft., scribed 1/4 S4 BT.  
A Fir 20" in dia. bears S73<sup>0</sup>W, 19.2 ft., scribed 1/4 S9 BT.  
Attached brass washer, stamped PLS 1051, to foot blaze of each BT.  
Attached 54-3 and 54-4 signs to each BT.  
Set painted metal fence post 5 ft. west of monument with 54-4 sign attached.  
Painted a 6" band around each BT and both blazes on each BT red.

---

Work Done By R. C. Orton Title Party Chief Date 12/7/80 State Registration No.  
or Agency \_\_\_\_\_

Certified Cor. Record Prepared ? Yes    No    Filed At: \_\_\_\_\_ Date \_\_\_\_\_

**REMARKS**

Witnesses to above corner: G. Lester

---

Index File No.

T.

R.

M.

Tract or Surv. No.

Cor.

12

13