


CERTIFIED RECORD OF LAND CORNER MONUMENTATION

Index File No. G-14

History of original corner establishment:

Not set.



Description of corner evidence found:

Description of monument and accessories established to perpetuate the original location of this corner:

New corner:

At surveyed point: set 2½"x30" galvanized pipe with brass cap marked:

From which a Fir 9" in diameter bears N89°E, 53.7 ft., scribed CW 1/16 S10 BT. A Fir 13" in diameter bears S02°W, 9.5 ft., scribed CW 1/16 S10 BT. Set pipe 22" in ground and built a mound of stones to the cap. Attached 54-3 and 54-4 signs to both BTs. Attached brass washer, stamped PLS 1051, to the foot blazes of both BTs. Painted a 6" band around the BTs and both blazes red. Set painted metal fence post 6 ft. south of corner with 54-2 and 54-9 signs attached. Set a painted metal fence post 5 ft. west of corner with 54-2 and 54-4 signs attached.

T4S R32E

CW 1/16 S10

C ——— | ——— C

1977

OR PLS 1051

I hereby certify the above corner monument was established as herein described.

Witnesses: R. Orton
G. Lester

December 8, 1980
See Record Survey Plat for S10, T4S, R32E, W.M. as filed with the Umatilla County Surveyor.



Office of County Surveyor County of Umatilla
Oregon, I hereby certify that the within instrument was filed in this office
 for record on the December day of 1980
David J. Sumner by Betty Shultz
 (COUNTY OFFICIAL) (DEPUTY)

G-14

R-187-B