

USDA-FOREST SERVICE


Index  
File No. G-15  
T 4S. R. 32E  
Merid. W.M.

CORNER RECORD (SEARCH)

(Ref. FSM 7151.4)

Tract or Survey No. \_\_\_\_\_ Cor. No. C1/4  
R.D. Ukiah County Umatilla  
N.F. Umatilla State Oregon

CORNER DIAGRAM



DESCRIBE CORNER MONUMENT FOUND

None Set.

DESCRIBE BEARING TREES OR OTHER OFFICIAL ACCESSORIES FOUND

None Set.

PHOTO IDENTIFICATION DATA

Photo No. \_\_\_\_\_  
Filed At. \_\_\_\_\_  
Object Ident. \_\_\_\_\_  
Ident. By \_\_\_\_\_  
*Signature*

PLANE COORDINATE POSITION DATA

State \_\_\_\_\_ Zone \_\_\_\_\_  
X \_\_\_\_\_  
Y \_\_\_\_\_  
Estab. By \_\_\_\_\_  
*Agency*

DESCRIBE CORNER LOCATION RELATIVE TO NEAR-BY FEATURES, ALSO HOW TO REACH CORNER

The corner lies on a steep southwest slope about 500 ft. southwest of the end of a lightly traveled road.

Signature

*Barry B. Barbour* P.L.S.

Title

Division

Headquarters

Date

10/31/77

7100-52 (3/68)

5

## CORNER RECORD (PERPETUATION)

MONUMENT: DESCRIBE NEW MONUMENT SET, OR WORK DONE TO PRESERVE EXISTING MONUMENT

T4S R32E

At surveyed point: Set 2½"x30" galvanized pipe with brass cap marked:

C1/4 S10

1977

OR PLS 1051

9

ACCESSORIES: DESCRIBE NEW BT'S WITNESS OBJECTS ETC. ESTABLISHED, OR WORK DONE TO PRESERVE EXISTING EVIDENCE

From which a Pine 9" in dia. bears N36°W, 78.9 ft., scribed C1/4 S10 BT. A Pine 10" in diameter S 30°W, 37.1 ft., scribed C1/4 S 10 BT. Set pipe 22 in. in ground and built a mound of stones to cap. Attached 54-3 and 54-4 signs to both bearing trees. Attached brass washer, stamped PLS 1051, to the foot blaze of both BT's. Painted 6 inch band and the blazes on both BT's red. Set painted metal fence post 3 ft. north of corner with 54-4 and 54-9 signs attached.

10

Work Done By R.C. Orton Title Party Chief Date 10/31/77 State Registration No. 68-100-0000  
or Agency

Certified Cor. Record Prepared? Yes No Filed At: Date 11

## REMARKS

Witnesses: G. Wagoner  
L. Clemens

12

Index File No. T. R. M. Tract or Surv. No. Cor. 13