

USDA-FOREST SERVICE

Index
File No. G-3


CORNER RECORD (SEARCH)

(Ref. FSM 7151.4)

Tract or
Survey No. _____ Cor.
No. C1/4

T 4S R. 32E R.D. Ukiah County Umatilla
Merid. W.M. N.F. Umatilla State Oregon

CORNER DIAGRAM



DESCRIBE CORNER MONUMENT FOUND

None Set.

DESCRIBE BEARING TREES OR OTHER OFFICIAL ACCESSORIES FOUND

None Set.

PHOTO IDENTIFICATION DATA

Photo No. _____
Filed At. _____
Object Ident. _____
Ident. By _____
Signature

DESCRIBE CORNER LOCATION RELATIVE TO NEAR-BY FEATURES, ALSO HOW TO REACH CORNER

Corner is about 300 feet east of track road on top of ridge in thick timber.

PLANE COORDINATE POSITION DATA

State _____ Zone _____
X _____
Y _____
Estab. By _____
Agency

Signature
Barry B. Barlow

Title
P.L.S.

Division _____ Headquarters _____

Date
11/14/77

7100-52 (3/68)

CORNER RECORD (PERPETUATION)

MONUMENT: DESCRIBE NEW MONUMENT SET, OR WORK DONE TO PRESERVE EXISTING MONUMENT

T4S R32E

Set 2½"x30" galvanized pipe with brass cap marked:

C1/4 + S7

Set pipe 22" in the ground with mound of stone around.

OR PLS 1051
1977

9

ACCESSORIES : DESCRIBE NEW BTs WITNESS OBJECTS ETC. ESTABLISHED, OR WORK DONE TO PRESERVE EXISTING EVIDENCE

A Pine 21" in dia. bears N20°E, 21.2 ft., scribed C1/4 S7 BT.

A Fir 12" in dia. bears N44°W, 11.5 feet, scribed C1/4 S7 BT.

Placed brass washer stamped PLS 1051 on foot blazes.

Placed 54-3s and 54-4s on both BTs.

Placed 54-2, 54-4 and 54-9 on fence post 4' north of corner.

Painted 6" red band around both BTs and painted both blazes red.

10

Work Done By B.B. Barbour Title P.L.S. Date 11/14/77 State Registration No. OR PLS 1051
for Agency

Certified Cor. Record Prepared ? Yes No Filed At: Date 11

REMARKS

Witnesses: D.L. Landers
S. Nelson

12

Index File No. T. R. M. Tract or Surv. No. Cor. 13