

USDA-FOREST SERVICE


Index
File No. H-1
T 4S R. 32E
Merid. W.M.

CORNER RECORD (SEARCH)

(Ref. FSM 7151.4)

R.D. Ukiah County Umatilla
N.F. Umatilla State Oregon
Tract or Survey No. _____ Cor. No. S1/16

CORNER DIAGRAM



DESCRIBE CORNER MONUMENT FOUND

None Set.

DESCRIBE BEARING TREES OR OTHER OFFICIAL ACCESSORIES FOUND

None Set.

PHOTO IDENTIFICATION DATA

Photo No. _____
Filed At. _____
Object Ident. _____
Ident. By _____
Signature

DESCRIBE CORNER LOCATION RELATIVE TO NEAR-BY FEATURES, ALSO HOW TO REACH CORNER

Corner falls in an open area, about 150 feet south of a small drain.

PLANE COORDINATE POSITION DATA

State _____ Zone _____
X _____
Y _____
Estab. By _____
Agency

Barney B. Barbour

Signature Title P.L.S. Division _____ Headquarters _____ Date 11/16/77
7100-52-(3/68)

CORNER RECORD (PERPETUATION)

MONUMENT: DESCRIBE NEW MONUMENT SET, OR WORK DONE TO PRESERVE EXISTING MONUMENT

Set 2½"x30" galvanized pipe with brass cap marked:
 Set pipe 18" in the ground to bedrock and mound of stone around.

OR PLS 1051
 T4S
 R31E | R32E
 S12 | S7
 S1/16
 1977

9

ACCESSORIES : DESCRIBE NEW BT'S WITNESS OBJECTS ETC. ESTABLISHED, OR WORK DONE TO PRESERVE EXISTING EVIDENCE

A Fir 14" in dia. bears S17⁰W, 9.4 ft., scribed S1/16, S12 BT. A Pine 15" in dia. bears N15⁰E, 50.2 ft., scribed S1/16, S7 BT. Placed 54-3s and 54-4s on BTs. Placed brass washer stamped PLS 1051 on foot blazes. Painted 6" red band and both blazes on BTs red. Placed 54-2 and 54-4 on fence post 4' South. Placed 54-2 and 54-9 on fence post 5' east of corner.

10

Work Done By B.B. Barbour Title P.L.S. Date 11/16/77 State Registration No. OR PLS 1051
 or Agency

Certified Cor. Record Prepared ? Yes No Filed At: _____ Date _____

11

REMARKS

Witness: Lyle Clemens

Index File No.

T.

R.

M.

Tract or Surv. No.

Cor.

12

13