


History of original corner establishment:

1881, George S. Pershin, U.S. Deputy surveyor, while surveying the township under General Land Office Contract No. 390 established the corner as follows:
Set basalt stone 14 X 12 X 4 on west slope of ridge for cor. to Sec. 9, 10, 15, & 16
A Fir 5 in. di. brs. N. 14° E. 45 lks. dis.
A Pine 7 in. di. brs. S. 45° E. 34 lks. dis.
A Pine 11 in. di. brs. S. 7° W. 46 lks. dis.
A Fir 7 in. di. brs. N. 45° W. 52 lks. dis.



1977, Craig L. Wanless, BLM Cadastral Surveyor, remonumented and described the corner as follows:
The cor. of secs. 9, 10, 15, and 16, monumented with the original unmarked basalt stone, 14 x 12 x 4 ins., loosely set 1 in. in the ground, from which the remains of the original bearing trees:
A pine, 22 ins. diam., bears S. 7° W., 46 lks. dist., with scribe marks T4S R visible on partially healed blaze.
A fir, 21 ins. diam., bears N. 26° W., 52 lks. dist., with healed blaze (Record, N. 45° W.)
At the corner point
Set an iron post, 28 ins. long, 2 1/2 ins. diam., 22 ins. in the ground, with brass cap
from which new bearing trees
A fir, 13 ins. diam., bears N. 77° E., 59 lks. dist., mkd. T4S R32E S10 BT.
A fir, 20 ins. diam., bears S. 34° E., 63 1/2 lks. dist., mkd. T4S R32E S15 BT.
Deposit corner stone alongside iron post.

1977, Barry B. Barbour, Registered Land Surveyor No. 1051, found the corner while surveying section 10 (Umatilla County Survey No. 0-69-A).


1992, William R. Wells, Registered Land Surveyor No. 1106, found and perpetuated the corner (Umatilla County Survey No. 92-80-B) as follows:
Found 2 1/2" iron pipe with 3 1/4" brass cap, no stone available
A 23" ponderosa pine brs S 3° W, 31.1' with scribing visible.
A 20" dead white fir brs S 34 3/4° E, 41.5' with scribing visible.
A 13" dead white fir brs N 77 1/4° E, 38.6' with scribing visible.
A 24" dead white fir brs N 26° W, 34.6' with healed blaze.
New bearing trees established:
A 17" ponderosa pine brs N 35 1/4° W, 327.1' scribed T4SR32ES9 BT.
A 13" western larch brs N 41° E, 25.0' scribed T4SR32ES10 BT.
A 23" ponderosa pine brs S 77 1/4° E, 94.5' scribed T4SR32ES15 BT.
New BT's have a brass washer stamped PLS 1106 nailed to face of blaze.

REGISTERED PROFESSIONAL LAND SURVEYOR
David A. Schlaich
OREGON JULY 16, 1987
DAVID A. SCHLAICH 2308

RENEWAL DATE: 06/30/2006

Description of corner evidence found:

Found a 2 1/2" iron pipe, with a 3 1/4" BLM brass cap, projecting 6" above the ground, with basalt stone visible on the West side of the monument, marked as shown, from which:
15" Western Larch bears N. 42° E., 25.0 feet with scribing visible on partially healed blaze and 3/4" brass washer "PLS 1106" nailed to the blaze (Wells's Record N. 41° E.).
13" White Fir snag bears N. 78 1/2° E., 38.6 feet, with scribing visible on partially healed blaze (Wanless's Record N. 77° E.).
23" Ponderosa Pine bears S. 75 1/2° E., 94.5 feet with scribing visible on partially healed blaze and 3/4" brass washer "PLS 1106" nailed to the blaze (Wells's Record S. 77 1/4° E.).
21" White Fir stump, bears S. 32 3/4° E., 41.5 feet, with scribing visible on partially healed blaze (Wanless's Record S. 34° E.).
26" Ponderosa Pine bears S. 4 1/4° W., 31.1 feet with scribing visible on partially opened blaze (Pershin's Record S. 7° W.).
18" Ponderosa Pine bears N. 33 3/4° W., 327.1 feet with scribing visible on visible on partially healed blaze and 3/4" brass washer "PLS 1106" nailed to the blaze (Wells's Record N. 35 1/4° W.).
22" White Fir snag bears N. 23 3/4° W., 34.6 feet, with healed blaze (Pershin's Record N. 45° W.).



Description of monument and accessories I established to perpetuate the original location of this corner:

DATUM: NAD83(1991)
STATE PLANE COORDINATES: Oregon North Zone in International Feet
Latitude Longitude Northing(y) Easting(x)
45°13'41.56777" North 118°50'22.51376" West 573690.970 8629838.232

Office of..... County of.....
State of....., I hereby certify that the within instrument was filed in this office for record on the..... day of....., 20.....
(COUNTY OFFICIAL) by..... (DEPUTY)