

USDA-FOREST SERVICE


Index File No. L-5
 T 4S R. 32E
 Merid. W.M.

CORNER RECORD (SEARCH)

(Ref. FSM 7151.4)

Tract or Survey No. _____ Cor. No. 1/4
 R.D. Ukiah County Umatilla
 N.F. Umatilla State Oregon

CORNER DIAGRAM



DESCRIBE CORNER MONUMENT FOUND

Found loose 10"x10"x9" basalt stone clearly marked 1/4. BLM tag on fence post marking approximate corner position.

2

DESCRIBE BEARING TREES OR OTHER OFFICIAL ACCESSORIES FOUND

Found 28" Pine stump with foot of blaze 6" from center of stump, but no visible scribing. BLM BT tag nailed on stump. No trace of SE BT could be found.

3

PHOTO IDENTIFICATION DATA

Photo No. _____
 Filed At. _____
 Object Ident. _____
 Ident. By _____
Signature

6

DESCRIBE CORNER LOCATION RELATIVE TO NEAR-BY FEATURES, ALSO HOW TO REACH CORNER

Corner is on the west side of a north-south fence and about 700' south of a private road bearing northwest into a canyon.

PLANE COORDINATE POSITION DATA

State _____ Zone _____
 X _____
 Y _____
 Estab. By _____
Agency

8

Signature

Barry B. Barbour P.L.S.

Title

Division

Headquarters

Date

10/21/77

7100-52-(3/68)

4

5

CORNER RECORD (PERPETUATION)

MONUMENT: DESCRIBE NEW MONUMENT SET, OR WORK DONE TO PRESERVE EXISTING MONUMENT

From Pine stump measured S63°E, 99.0' and set 2½" x 30" galvanized pipe with brass cap marked:

Pipe is set 15" in the ground to bedrock and mound of stone to cap. Placed marked stone at base of pipe.

T4S R32E
1/4
S18 + S17
OR PLS 1051
1977

9

ACCESSORIES: DESCRIBE NEW BT'S, WITNESS OBJECTS ETC. ESTABLISHED, OR WORK DONE TO PRESERVE EXISTING EVIDENCE

A Pine 12" dia. bears N41°E, 18.0', scribed 1/4 S17 BT.

A Pine 12" dia. bears S46°W, 22.6', scribed 1/4 S18 BT.

Placed 54-3s and 54-4s on trees, brass washer on BT blaze, marked PLS 1051.

Painted 6" red bands and both blazes red.

Placed 54-4 on existing fence post 3' south.

10

Work Done By B.B. Barbour Title P.L.S. Date 10/21/77 State Registration No. OR PLS 1051
or Agency

Certified Cor. Record Prepared? Yes No Filed At: _____ Date _____

11

REMARKS

Witness to the above corner: D.L. Landers
S. Nelson

12

Index File No. T. R. M. Tract or Surv. No. Cor.

13