

USDA-FOREST SERVICE

Index File No. M-19
T 4S R. R32E
Merid. W.M.


CORNER RECORD (SEARCH)

(Ref. FSM 7151.4)

Tract or Survey No. _____
Cor. No. SC1/16
County Umatilla
State Oregon

R.D. Ukiah
N.F. Umatilla

CORNER DIAGRAM



DESCRIBE CORNER MONUMENT FOUND

None set.

DESCRIBE BEARING TREES OR OTHER OFFICIAL ACCESSORIES FOUND

None set.

PHOTO IDENTIFICATION DATA

Photo No. _____
Filed At. _____
Object Ident. _____
Ident. By _____
Signature

PLANE COORDINATE POSITION DATA

State _____ Zone _____
X _____
Y _____
Estab. By _____
Agency

DESCRIBE CORNER LOCATION RELATIVE TO NEAR-BY FEATURES, ALSO HOW TO REACH CORNER

Corner falls on west slope in scattered timber.

Barney B Barbour

Signature

Title
P, L, S.

Division

Headquarters

Date

11/28/77

7100-52-(3/68)

5

CORNER RECORD (PERPETUATION)

GPO 902-673

MONUMENT: DESCRIBE NEW MONUMENT SET, OR WORK DONE TO PRESERVE EXISTING MONUMENT

At surveyed point set 2½"x30" galvanized pipe with brass cap marked:
Set pipe 20" in the ground with mound of stone around.

T48 R32E
SC 1/16
+
S 14
OR PLS 1051
1977

ACCESSORIES: DESCRIBE NEW BT'S, WITNESS OBJECTS ETC. ESTABLISHED, OR WORK DONE TO PRESERVE EXISTING EVIDENCE

From which a fir 14" in dia. bears N89°E, 19.2 feet, scribed SC1/16 S14 BT. A pine 11" in dia. bears S55°E, 27.1 feet, scribed SC1/16 S14 BT. Placed 54-3s and 54-4s on both trees, brass washer on foot blazes stamped PLS 1051. Placed 54-2 and 54-4 on fence post 4' east of corner. Painted 6" red bands and painted both blazes red.

Work Done By B.B. Barbour Title P.L.S. Date 11/28/77 State Registration No. OR PLS 1051
Agency

Certified Cor. Record Prepared? Yes No Filed At: _____ Date _____

REMARKS

Witness to above corner: L. Clemens