

CERTIFIED RECORD OF LAND CORNER MONUMENTATION


N-11

History of original corner establishment:

Corner originally established by George S. Pershin, U.S. Deputy Surveyor, under Contract No. 390, dated May 12, 1881. Surveyor General records state: Set basalt stone 20x12x10 in open glade on S.W. slope for 1/4 Sec. Cor. A pine 30 in. di. brs. N55°E, 179 lks. dist. A pine 13 in. di. brs. S34°E, 95 lks dist.

Corner remonumented by Craig L. Wanless, BLM Cadastral Surveyor under instructions dated July 18, 1977. His record states: The 1/4 sec. cor. of secs. 16 & 21, monumented with the original unmarked basalt stone, 20x12x10 ins., firmly set in a mound of stone, 3 ft. base, 6 ins.

high, from which the original bearing trees: A pine 37 ins. diam, bears N55°E, 182 lks. dist., with scribe marks 1/4 S visible on open double blaze. (record, 179 lks.) A pine 26 ins. diam., bears S25°E, 99 lks. dist., with healed blaze. (record, S34°E, 95 lks.) At the corner point... Set an iron post, 28 ins. long, 2 1/2 ins. diam., 10 ins. in the ground, to solid rock, and in a mound of stone, 3 ft. base, to top, with brass cap mkd. (as shown in corner diagram). Deposit corner stone alongside iron post.



Description of corner evidence found:

Found 2 1/2" iron pipe with 3 1/4" brass cap (as shown in corner diagram) in mound of stone.

- A 38" ponderosa pine brs N52°E, 119.3' with scribing visible.
- A 27" ponderosa pine brs S26 1/2°E, 65.4' with healed blaze.

Description of monument and accessories established to perpetuate the original location of this corner:

Set steel fence post next to corner with sign 54-9 & 54-2 attached.

New bearing trees established:

- A 19" ponderosa pine brs S35 1/2°E, 32.6' scribed 1/4 S 21 BT
- A 11" ponderosa pine brs N46°E, 79.6' scribed 1/4 S 16 BT.

New BT's have a brass washer stamped PLS 1106 nailed to face of blaze. Attached sign 54-3 & 54-9, painted face of blaze & a 6" red band around each BT.

Compass declination 18° East.

I hereby certify that the above corner monument was properly maintained to U.S.F.S. standards by me on June 03, 1992.

REGISTERED
PROFESSIONAL
LAND SURVEYOR

William R. Wells

OREGON
JULY 22, 1977
WILLIAM R. WELLS
1106

Office of... County Surveyor..... County of... Umatilla
Oregon
State of....., I hereby certify that the within instrument was filed in this office
for record on the..... day of....., 19.....
..... by
(COUNTY OFFICIAL) (DEPUTY)

Form R6-7100-57 (9/71)

RECEIVED BY
Umatilla County Surveyor
Date 7-9-92
Rec'd By KK
No. 92-80-B

☆ GPO-788-276

N-#