

CERTIFIED RECORD OF LAND CORNER MONUMENTATION

INDEX No. N-23

History of original corner establishment:

This corner was originally established George Pershin, in 1881, under GLO Contract No. 390. Surveyor General Field Notes state:

DIAGRAM
T4S R32E
1/4 S13
S24
1994
PLS 2405

Set basalt stone 16x12x8 on slight east slope for 1/4 cor.

A pine 20 in. dia. bears N5°W, 95 lks dist.
A pine 12 in. dia. bears S43°E, 55 lks dist.

Description of Corner Evidence Found:

Found 16"x12"x8" basalt stone clearly marked 1/4 on north face. Stone was set 8" deep.

Found no remains of the original bearing trees

Description of monument and accessories I established to perpetuate the original location of this corner:

Moving the original corner stone aside I set in it's place a 2-1/2"x30" aluminum pipe with 3-1/2" aluminum cap, stamped as shown on the DIAGRAM, 26" in the ground and placed original stone north alongside.

From Which:

- Ponderosa Pine, 11" dia., bears N61°45'W, 32.3 ft., scribed: 1/4 S13 BT
- Ponderosa Pine, 14" dia., bears N32°30'E, 35.8 ft., scribed: 1/4 S13 BT
- Ponderosa Pine, 14" dia., bears S58°45'E, 30.8 ft., scribed: 1/4 S24 BT
- Ponderosa Pine, 14" dia., bears S43°30'W, 9.9 ft., scribed: 1/4 S24 BT

Measurements to BT's taken with a magnetic compass, declination 20° East, and a nylon clad steel tape. Set steel fence post with Land Survey Monument (54-9) sign 5' south of the monument. Nailed a brass washer stamped PLS 2405 on blaze above BT scribe as taken this survey. Nailed Bearing Tree (54-3) signs above blaze and Land Survey Monument (54-9) signs on back of each tree as required. Painted a 6" red band above Bearing Trees signs.

REGISTERED
PROFESSIONAL
LAND SURVEYOR

Susan E. Newstetter

OREGON
JULY 25, 1989
SUSAN E. NEWSTETTER
2405

Renewal Date 12/31/96

This work was performed by:
Susan E. Newstetter PLS 2405
Witnessed by: Rick Saul and
Rick Pewonka
October 18, 1994

RECEIVED BY

Umatilla County Surveyor
Date 1-95
Rec'd By BK
No. 95-15-B

Office of _____ County of _____
State of _____ I hereby certify that the within instrument was
filed in this office for record on the _____ day of _____, 19____
by _____

(COUNTY OFFICIAL)

(DEPUTY)

N-23