

CERTIFIED RECORD OF LAND CORNER MONUMENTATION

INDEX No. T.25-22.25

History of original corner establishment:

None. Corner established this survey.

DIAGRAM
S25
NW-NE-SW
1/256
1994
PLS 2405

Description of Corner Evidence Found:

None. Corner established this survey.

Description of monument and accessories I established to perpetuate the original location of this corner:

Set 2-1/2"x30" aluminum pipe with 3-1/2" aluminum cap, stamped as shown on the DIAGRAM, 8" in the ground and raised a mound of earth and stone, 4 ft. dia. x 2 ft. high.

From Which:

Pond. Pine, 8" dia., bears N68°46'W, 37.0 ft., scribed: NW-NE-SW 1/256 S25 BT

Pond. Pine, 12" dia., bears N62°02'E, 20.0 ft., scribed: NW-NE-SW 1/256 S25 BT

Measurements to BT's taken with an Electronic Tacheometer with bearings based on the survey control network. Set steel fence post with Land Survey Monument (54-9) and Property Boundary (54-2) signs 5' north and west of the monument. Nailed a brass washer stamped PLS 2405 on blaze above BT scribe as taken this survey. Nailed Bearing Tree (54-3) signs above blaze and Land Survey Monument (54-9) signs on back of each tree as required. Painted a 6" red band above Bearing Trees signs.



Renewal Date: 12/31/96

This work was performed by:
Susan E. Newstetter PLS 2405
Witnessed by: Rick Saul and
Rick Pewonka
October 26, 1994

RECORDED BY
Umatilla County Surveyor
Date 1-95
Rec'd By KK
No. 95-15-B

Office of _____ County of _____
State of _____ I hereby certify that the within instrument was
filed in this office for record on the _____ day of _____, 19____
by _____

(COUNTY OFFICIAL)

(DEPUTY)