

Index
File No. O-14

CORNER RECORD (SEARCH)

(Ref. FSM 7151.4)

Tract or Survey No. _____ Cor. No. _____

T 4 S R. 32 E R.D. Ukiah County Umatilla
Merid. Willamette N.F. Umatilla State Oregon

CORNER DIAGRAM

T 4 S R 32 E

NW 1/16

S 22

1992

PLS 1106



DESCRIBE CORNER MONUMENT FOUND

None. Corner established as part of this survey.

DESCRIBE BEARING TREES OR OTHER OFFICIAL ACCESSORIES FOUND

Found Kinzua location poster on a 15" douglas fir which brs S68°W, 10' ± from corner point.

PHOTO IDENTIFICATION DATA

Photo No. _____

Filed At. _____

Object Ident. _____

Ident. By _____

Signature

PLANE COORDINATE POSITION DATA

State _____ Zone _____

X _____

Y _____

Estab. By _____

Agency

Signature

Walter R. Wells

Title

Land Surveyor

Division

Headquarters

Pendleton, Ore.

Date

6-12-92

FS-7100-52 (3/68)

CORNER RECORD (PERPETUATION)

MONUMENT: DESCRIBE NEW MONUMENT SET, OR WORK DONE TO PRESERVE EXISTING MONUMENT

At position established by survey...

Set a 2 1/2"x30" aluminum pipe with 2 1/2" aluminum cap 19" in ground surrounded with mound of earth and stone. Set steel fence post South of corner and attached signs 54-2 & 54-9. Cap marked as shown in corner diagram. Compass declination 18° East.

9

ACCESSORIES : DESCRIBE NEW BT'S WITNESS OBJECTS ETC. ESTABLISHED, OR WORK DONE TO PRESERVE EXISTING EVIDENCE

New bearing trees established:

A 18" ponderosa pine brs N23 1/2° W, 112.6' scribed NW1/16S22 BT.

A 13" ponderosa pine brs N55 1/2° E, 78.8' scribed NW1/16S22 BT.

New BT's have a brass washer stamped PLS 1106 nailed to face of blaze.

Attached sign 54-3 & 54-9, painted face of blaze & a 6" red band around each BT.

10

Work Done By. W.R. Wells Title Land Surveyor Date 6-12-92 State Registration No. ORLS 1106 or Agency

Certified Cor. Record Prepared ? Yes XXX Filed At: Umatilla County Surveyor Date 7-92

11

REMARKS

12

13

Index File No. O-14 T. 4 S. R. 32 E. M. WM. Tract or Surv. No.

Cor.